

SURVEY & REMONUMENTATION

FILED

APR 25 1995

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE DEC 5 2 48 PM '94
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

VAN BUREN

(County)

Located In:
Decatur Twp.

Corner Code #

Mark A. Smith
 VAN BUREN CO.
 REGISTER OF DEEDS

- | | | | | |
|------------------------------------|------------|--------|---------|------------|
| 1. Public Land Survey | Sec. 18 | T 4 S. | R 14 W. | <u>A-6</u> |
| | W 1/2 Post | T | R | |
| | | T | R | |
| | | T | R | |
| 2. Property Controlling in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous Property in Sec. | S | T | R | |
| | S | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Hunt, P.S. in a field survey on Nov. 29, 1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 W 1/2 Post of Sec. 18 T4S-R14W, Red Book shows jog S. to Hamilton Twp. corner of 1.51 chs. (99.66'). 4/1962 W.Q. Smith CS, drawing shows corner: shows distance E. of 2014.58' to center 1/2 post, continued E. to E 1/2 post 2643.54' for total of 4658.12'; distance S. to C/L of road 1019.29' & continued S. 1629.59' to section corner for a total of 2648.88'; distance N. to 1/8 post 1324.32' & continued N. 1324.32' to section corner for total of 2648.64'.

Retified by Peer Group in accordance with P.A. 345 of 1990
 Van Buren County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 W 1/2 Post of Sec. 18 T4S-R14W, Decatur Township.
 Corner evidence found: Found pointed stone. Replaced with Harrison marker and placed survey marker Witness Post alongside.

Date J. P.S. 12/5/94


THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

THE POSITION OF THIS GOVERNMENT MONUMENT WAS ESTABLISHED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON APRIL 13, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 HARRISON MARKER

- S.02°E. 84.25' Set PK nail & washer in W. face of 9" Ash.
- N.25°W. 4.20' Set PK nail & washer in E. face of 16" Oak.
- N.56°E. 29.33' Set PK nail & washer in N. face twin 12"-13" Oak.
- S.27°W. 29.78' Set PK nail & washer in W. face of 19" Oak.



Signed by John C. Hunt, P.S.
 Surveyor's Michigan License No. 23513

Date Dec. 1, 1994