

RECORDED

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 2 2 54 PM '93

COMMISSION

For corners in Decatur Township
Van Buren County
(County)

Located In:

Corner Code #

- 1. Public Land Survey 4SR 14W 7B
SXP, Section 18
T R
T R
T R
T R
- 2. Property Controlling
in Section S T R
S T R
- 3. Miscellaneous
Property in Sec. S T R
S T R

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

9.00
0101 10SURVEY

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald R. Gilchrist, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/1830 - GOVERNMENT - E.H. Lytle, D.S.
Ran West - Set 1/4 Section Post at 40.00 chs.
Witnesses: 7" White Oak - N 22 Deg E - 23 lks. (15.15')
6" White Oak - S 52 Deg W - 7 lks. (4.62')

10/29/1908 - Ackley, C.S.
Stone & Stake
Witnesses: 28" B. Oak - S 1 Deg 30' E - 12 lks. (7.92')
(Continued on back of Certificate)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 3/4" pipe with small stones, around beside a stone/cone on top, over a larger stone.
Set Harrison Marker at pipe location

This Corner approved at Van Buren County Peer Group Meeting of 8/25/93 and is accepted as a careful and faithful perpetuation of the original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 90" B.Oak - S 5 Deg E - 10.35'
- 90" B.Oak - West - 85.74'
- P.P. - S 45 Deg W - 87.75'
- 8" Maple - North - 85.28'
- Plat Mon - N 10 Deg W - 6.83'
- CL Rd - S - 33'
- CL Rd - N 15 Deg W - 58'



Signed by Donald R. Gilchrist Date 11/23/93
Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583

LIBER 4 PAGE 84

LIBER 4 PAGE 85

A. Continued from front of Certificate

24" White Oak - S 73 Deg W - 46 lks. (30.36')

5/16/1932 - T.A. Smith, C.S.

Found Stone & Stake, Drove Iron over

Measured South 1326.0' to 1/8 Post and continued South 1326.0' to
Center 1/4 Post

1960± - Tax Description Office

Sketch shows distance from NE Corner to NW Corner

11/3/1972 - W.Q. Smith, C.S. (Dennis Middleton, R.L.S.)

Survey recorded (L3-P102)

11/14/1962 - Corner Recordation Certificate (L2-P9)

8/11/1976 - D.R. Gilchrist, C.S. (Gove Assoc.)

Survey Recorded (L6-P153)

3/5/1982 - Charles Glasner, R.L.S. (Gove Assoc.)

Plat of Lakeview Park No. 3, Recorded L8-P30, 31, 32 & 33)