

JAN 14 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
VAN BUREN COUNTY REMONUMENTATION

DEC 23 8 59 AM '97

SECTION

For corners in VAN BUREN (County)

Located In: Corner Code #

- 1. Public Land Survey S 1/4 Sec 31 Decatur Twp. T 4S R 14W B-13
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Mark A. Smith VAN BUREN CO. SURVEYOR

Liber 5 Page 82

Register of Deeds Stamp & File Number

7.00 12/23 0101 105URVEY

- 4. Lot No. Recorded Plat
5. Private Claims

I, DALE L. KESLER, in a field survey on NOV. 13, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
\*1827 WILLIAM BROOKFIELD. WEST 40.00 CHAINS QUARTER SECTION CORNER ON A POPLAR 40"

\*NOV. 3, 1875 AMOS SMITH. IDENTIFIED, SET STONE ABOVE STAKE. 12" BEECH S 8 3/4 DEGREES W 24 LKS., 12" BEECH N 62 DEGREES W 33 LKS.

\*JUNE 15, 1898 GEORGE MUCHLER. FOUND STUMP AND STAKE. 16" BEECH N 62 DEGREES W 36 KS., 24" SUGAR N 52 3/4 DEGREES E 48 LKS.

\*APRIL 11, 1956 W.O. SMITH. MEASUREMENTS WERE MADE TO CONFIRM FACT THAT SW FR 1/4 AGREES WITH DIMENSIONS OF GOVERNMENT SURVEY.

\*APRIL 10, 1971 D.M. DREHER COMPLETED SURVEY WHICH INDICATED 3/4" IRON FOUND AT NORTH QUARTER CORNER OF SECTION 6. SURVEY INDICATED OLD WITNESSES TO STONE GONE. CENTER OF 12" MAPLE S 10 DEGREES E, 25.6', CENTER OF 12" MAPLE N 5 DEGREES E, 22.8', CENTER OF 24" TREE N 75 DEGREES E, 13.6', CENTER OF 18" BEECH S 65 DEGREES W 19.3', OLD FENCE CORNER 3' EAST AND 3' SOUTH.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE. THE 12" MAPLE N 5 DEGREES E 22.80' WITNESS FROM THE APRIL 10, 1971 SURVEY BY D.M. DREHER VERIFY LOCATION OF CORNER. ACCEPTED 3/4" IRON PIPE AS BEST EVIDENCE OF CORNER. THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION GROUP OF SURVEYORS AT A MEETING HELD ON NOVEMBER 20, 1997 AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET HARRISON MARKER IN PLACE OF 3/4" IRON PIPE. STEEL FENCE POST NORTH 0.55' FENCE LINE EAST AND WEST 3.0' SOUTH NAIL & TAG 20" BIRCH S 44 DEGREES W 18.75' NAIL & TAG 18" MAPLE S 32 DEGREES E 25.10' NAIL & TAG 4" OAK N 45 DEGREES W 30.25'



Signed by Dale Kesler

Date 12/13/97

Surveyor's Michigan License No. 38117

Grid table with columns A-M and rows 1-13. A dot is marked at row 13, column A.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date D. R. G. 12/23/97