

# SURVEY & REMONUMENTATION

FILED

APR 25 1995

VAN BUREN COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 3 43 PM '94

For corners in

VAN BUREN

(County)

Located In:  
Decatur Twp.

Corner Code #

- |                         |                      |                              |            |
|-------------------------|----------------------|------------------------------|------------|
| 1. Public Land Survey   | Sec. 21              | T <u>4</u> S. R <u>14</u> W. | <u>E-8</u> |
|                         | W $\frac{1}{4}$ Post | T _____ R _____              | _____      |
|                         |                      | T _____ R _____              | _____      |
|                         |                      | T _____ R _____              | _____      |
| 2. Property Controlling | S _____              | T _____ R _____              | _____      |
| in Section              | S _____              | T _____ R _____              | _____      |
| 3. Miscellaneous        | S _____              | T _____ R _____              | _____      |
| Property in Sec.        | S _____              | T _____ R _____              | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

*Mark A. Smith*  
VAN BUREN CO.  
REGISTER OF DEEDS

7.00  
12/21 0101 10SURVEY

LIBER 4 PAGE 228

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S., in a field survey on Nov. 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/1830 GOV.: EH Lytle DS, Set  $\frac{1}{4}$  Post, Wit.: 8" White Oak N80°W 16 lks, 16" White Oak N8°W 39 lks. 4/10/1899 G Mutchler CS: Worked in Sec. 20 & fd. nothing at E $\frac{1}{4}$  post. 1900+-WH Goss CS: Fd. nothing at E $\frac{1}{4}$  post. 4/30/1938 TA Smith CS: drawing shows cor. On 5/11/1946 he drove pipe in line w/ fence South & Wit.: 15" Oak N. 112.3' to C/L, 8" Cherry N50°E 66.4' to C/L, 4' S. of C/L of blacktop. He meas. N. 1336.8 to 1/8 post & N. 1336.8' to Sec. cor. He meas. W. 1316.3' to 1/8 post & 1316.3' to center of section. In 1975 Smith & Smith showed same dist. to center of section. 5/17/1979 DR Pitts PS; Rec. Cert. L.2 p.588. 6/11/1979 DR Pitts PS, Rec. Cert. L.2 p.567. 12/10/1991 R Stephenson PS, Recorded survey L.9 p.283.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 Corner common to Sections 20 & 21, T4S-R14W, Decatur Township.  
Corner evidence found: Found 3/4" iron pipe 4' S. of centerline of road East & West (C.R. 358) and 16" W. of centerline of road to North (42nd St.) and in line with tree row to South. Removed and set Harrison Marker in monument box.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 29, 1994, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group in  
accordance with P.A. 345 of 1990  
Van Buren County Surveyor

Date S.P.A. 12/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 HARRISON MARKER IN MONUMENT BOX.

- N.27°E. 77.11' Set PK nail & washer in East face pole.
- S.03°W. 18.58' Set PK nail & washer in East face pole.
- S.60°W. 44.45' Set PK nail & washer in N. face of 9" dia. Pine.
- N.15°W. 88.37' Set PK nail & washer in E. face of 12" Oak.

Signed by John C. Hunt, P.S.  
Surveyor's Michigan License No. 23513

Date Dec. 15, 1994

