

VAN BUREN COUNTY REMONUMENTATION PROGRAM

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 7 1 37 PM '98

For corners in Decatur Twp.

Van Buren (County)	Located In:	Corner Code #:
1. Public Land Survey W $\frac{1}{4}$ Post Sec. 22	T 4S R 14W	G-8
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat JAN 11 1999

5. Private Claims _____

SECTION

I, John C. Hunt, P.S., in a field survey on June 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1830 Gov.: W.Brookfield DS ran N. bet. Sec. 21 & 22 2640' & set $\frac{1}{4}$ post. Wit.: 9" B.Ash N58°E 5.28'; 9" B.Ash S50°W 33.0'. 4/18/1929 T.Smith CS couldn't find W $\frac{1}{4}$ post. Ran W. line Sec. 22: It comes 13.3' E. of C/L of culvert across rd. Put bolt & brick on top of culvert in C/L of rd. E. to center $\frac{1}{4}$ post is 2656.1'. Set corner 332' E. & cont. E. 332' & cont. E. 664.05' to 1/8th post 1328.05'. 4/22/1960 W.Smith CS Fd. iron at $\frac{1}{4}$ post. N. to NW cor. of sec. is 2657.65'. Set point 664.41' N. of $\frac{1}{4}$ post. 8/6/1969 Smith crew: Corner gone. Fd. E $\frac{1}{4}$ post: Old wit. stump good. Iron 2' S. of C/L of travel. Fd. ROW iron at SE cor. Becker house. This line extended W. to C/L 48" culvert on apparent W. line of sec. Set 80p spike. This came on very S. edge of paving using dist. 2659.3' from Red Bk. for E. half; agrees w/ major occupation. Dist. W. to C/L culvert is 5321' giving dist. for W. $\frac{1}{4}$ of 2661.7'. Staked parcel with 221.76' frontage. 8/22/1969: Drawing shows above parcel & W $\frac{1}{4}$ post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

W $\frac{1}{4}$ Post Sec. 22 (G-8), (Quarter post common to Sections 21 & 22) T4S-R14W, Decatur Twp., Van Buren Co., Michigan:

No corner found. Re-established corner at midway point between the NW corner of Sec. 21 T4S-R14W, and the SW corner of Sec. 22 T4S-R14W, Decatur Twp., Van Buren Co., Michigan. Set Harrison Marker and Monument Box in centerline of road and 9' East of C.M.P. under road.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON FEBRUARY 25, 1998, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 HARRISON MARKER IN MONUMENT BOX

S84°E 114.00' Set mag. nail in N. face of pole.
N25°E 48.58' Set mag. nail in E. face of 12" red maple.
N54°E 73.37' SE corner house foundation.
N15°W 27.57' N. end at C/L drainage tube.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date S.R.G. 12-7-98



Signed by John C. Hunt

Date Oct 12, 1998

Surveyor's Michigan License No. 23513