

VAN BUREN COUNTY REMONUMENTATION PROGRAM

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 11 2 58 PM '98

For corners in Decatur
Van Buren

Located In: _____ Corner Code # _____

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

- 1. Public Land Survey T4S R 14W _____ H-7
S $\frac{1}{4}$ Post Sec. 15 T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____ SURVEY &
Property in Sec. S _____ T _____ R _____ REMONUMENTATION

Liber 5 PAGE 170

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat JAN 11 1999
- 5. Private Claims _____

SECTION

John C. Hunt, P.S. Sept. 28 98

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7 1830 Gov.: Wm Brookfield DS ran E. bet. sec. 14 & 22 80.20 chs (5293.20'), corrected, & set $\frac{1}{4}$ post stake at 40.10 chs. (2646.6'). 11/8/1906 WH Goss CS: Sec. 15 Bk. 7 p.80 red bk. & notes: Dist. E. is 10.02 chs. (661.32') & cont. E. for a total of 2645.28' (Red Bk. & notes = 2644.62'). Dist. W. is 5.1 chs (330.66') & cont. W 15.025 chs. (991.65') to 1/8th post & cont. W 20.035 chs. (1322.31') to SW cor. for total of 2644.62'. Dist. N is 40.06 chs (2643.96'). 11/12/1980 JC Hunt RLS: Sec. 15 Survey Map: No cor. set (in line w/ tree row to S). Dist. N is 2648.8' to center of sec. (iron pipe) & cont. N 2640.00' to N $\frac{1}{4}$ post for total of 5288.80'. Dist. W is 2624.36' to SW corner. Dist. E is 2662.76' to SE corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Quarter post common to Sections 15 & 22, T4S-R14W, Decatur Twp., Van Buren Co., MI: Corner evidence found: None. Corner is in drainage ditch. Re-established quarter post by setting an 8' long range pole with cap #23513 & Witness post at corner, being 2' N. of S. edge of water in drainage ditch. Note: Top of range pole is 2' above water level.

Note: N89°29'26"W 2653.65' to NW corner of Sec. 22 T4S-R14W, and S89°29'26"E 2653.65' to NE corner of Sec. 22 T4S-R14W:

THIS GOVERNMENT MONUMENT WAS RE-ESTABLISHED AT THE MIDWAY POINT BETWEEN THE SOUTHWEST AND SOUTHEAST CORNERS OF SECTION 15, T4S-R14W, DECATUR TWP., VAN BUREN CO., MI WITH APPORVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON FEB. 25, 1998, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 8' long Range Pole with cap #23513 and Witness Post in drainage ditch.

Witnessed by 4 mons:

- Set mon 18' North of corner at top bank of ditch.
- Set mon 18' North and 50' East of corner at top bank of ditch.
- Set mon 10' South of corner at top bank of ditch.
- Set mon 10' South and 50' West of corner, 3' South of top bank of ditch.



Signed by John C. Hunt, P.S.
Surveyor's Michigan License No. 23513

Date December 9, 1998
Ratified by Peer Group in accordance with P.A. 345 of 1998
Van Buren County Surveyor

3190 12/11 0101 10SURVEY 7.00
Date D. R. A. 12-11-98