

JAN 14 1998

DEC 23 8 59 AM '97

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
VAN BUREN COUNTY REMONUMENTATION

For corners in

VAN BUREN

(County)

Located In:

Corner Code #

1. Public Land Survey
NW COR. SEC. 2
NW COR. SEC. 3
DECATUR TWP.

T 4S R 14W

I-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, DALE L. KESLER, in a field survey on NOV. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

\*1827 WILLIAM BROOKFIELD. SET POST CORNER TO SECTIONS 34 & 35, 18" OAK N 17 1/4 DEGREES W 23.83 LKS., 10" OAK W 12.90 LKS.

\*JUNE 9, 1900 GEORGE MUTCHLER (COUNTY SURVEYOR). STONE PRESENT WITNESS VERY DISTANT TO FIND NOW. RE-WITNESS: 2" ASH N 2 DEGREES E 46 1/4 LKS., 28" OAK N 88 3/4 DEGREES W 12.93 LKS.

\*AUG. 30, 1905 J.S. HAINES. FOUND STONE.

\*SEPT. 16, 1912 W.V. ACKLEY. MAKES REFERENCE TO MUTCHLER SURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BOLT IN ASPHALT, DUG BELOW, FOUND STONE. DISTANCES TO ADJACENT CORNERS WERE REASONABLE AND CONSISTENT. ACCEPTED 1/2" BOLT AS BEST EVIDENCE OF CORNER. THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION GROUP OF SURVEYORS AT A MEETING HELD ON DECEMBER 3, 1997, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET HARRISON MARKER IN PLACE OF 1/2" BOLT IN A MONUMENT BOX.

FENCE CORNER POST S 36 DEGREES 58' E 36.03'

NAIL & TAG POWER POLE S 32 DEGREES 55" W 41.73'

R R FENCE POST S 36 DEGREES 57' W 38.64'

NAIL & TAG POWER POLE N 10 DEGREES 41' W 31.77'

NAIL & TAG 12" HICKORY S 48 DEGREES 18' W 60.20'



Signed by Dale L Kesler

Date 12/22/97

Surveyor's Michigan License No. 38117

Mark A. Smith
VAN BUREN CO.
COUNTY SURVEYOR

Lib 5 Page 89

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor
Date B. R. L. 12/23/97