

SURVEY & REMONUMENTATION

FILED

APR 25 1995

VAN BUREN COUNTY REMONUMENTATION PROGRAM

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

DEC 21 3 43 PM '94

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Corner common to Sec. 35 & 36

VAN BUREN

(County)

Located In:

Decatur Twp.

Corner Code #

Mark A. Smith
VAN BUREN CO.
REGISTERED SURVEYOR

- | | | | |
|-------------------------|---------|------------------------------|-------------|
| 1. Public Land Survey | Sec. 36 | T <u>4</u> S. R <u>14</u> W. | <u>K-13</u> |
| | SW Cor. | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling | S _____ | T _____ R _____ | _____ |
| in Section | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ | T _____ R _____ | _____ |
| Property in Sec. | S _____ | T _____ R _____ | _____ |

LIBER 4 PAGE 229

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Hunt, P.S., in a field survey on Dec. 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

4/1827 GOV.: W. Brookfield DS, set post corner for Sec. 35 & 36, 40 chs. from S $\frac{1}{2}$ post. Wit.: 14" Burr Oak N7 $^{\circ}$ 30'E 734 lks., 15" Burr Oak N43 $^{\circ}$ 15'W 1062 lks. 1900+- W.H. Goss CS, Red Book for Decatur shows stone, Wit.: Sugar SE 52 lks., Sugar SW 81 lks. Meas. E. 19.94 chs to 1/8 post, cont. E. 19.94 chs to $\frac{1}{4}$ post for a total of 2632.08'. 9/16/1912 W.V. Ackley CS, Book 7 p.185, fd. stone, Gov. wit. still standing. 9/15/1941 T.A. Smith CS, Red Book, meas. W. 1322.9' to 1/8 post, set spike in C/L of road (a pipe 33' N.) cont. W. 1322.9' to $\frac{1}{4}$ post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner common to Sections 35 & 36, T4S-R14W, Decatur Township.
K-13 Corner evidence found: 1" iron pipe over small stone 2' below surface. Removed & set Harrison Marker in mon box 1' S. of C/L road E. & W. & 1' W. of C/L road N. & S.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION GROUP OF SURVEYORS AT A MEETING HELD ON JUNE 29, 1994, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Validated by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date S.P.A. 12/21/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 HARRISON MARKER IN MONUMENT BOX

- N.40 $^{\circ}$ W. 44.41' Set PK nail & washer in E. face of pole.
- S.32 $^{\circ}$ W. 53.45' Set PK nail & washer in N. root of 36" Maple.
- S.12 $^{\circ}$ W. 111.56' Set PK nail & washer in E. face of 32" Maple.
- S.43 $^{\circ}$ E. 42.66' centerline of telephone cable box.

Signed by John C. Hunt, P.S.
Surveyor's Michigan License No. 23513

Date Dec. 7, 1994

