

**SURVEY &
REMONUMENTATION**

FILED

SEP 18 1997

FEB 3 3 21 PM '97

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Mark A. Smith
VAN BUREN CO
REGISTER OF DEEDS

7.00

For corners in

Van Buren Co., Hamilton Twp. Located In: Corner Code #
(County)
S.W. COR. SEC. 29
1. Public Land Survey T 4 S R 15 W C-11
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

LIBER 4 PAGE 491
Register of Deeds Stamp & File Number
5448 02/03 0101 105URVEY

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James E. Boynton, in a field survey on January 8, 1997
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Location of original corner established in 1830 by E. H. Lytle, D.S. Sleigh shoe surrounded by brick set in place from one witness tree and remains of old stake in 1871 by A. J. Pierce, C.S. "Iron Stake" found from one witness and used by G. Muchler, C.S. in 1898. This corner was used again in 1947 and 1953 by T. A. Smith, C.S. and W. Q. Smith, C.S. but no indication of physical character given. The corner was also used by the Highway Department but no indication of physical character given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found sleigh shoe and brick after checking distances both North and East against Muchler 1898 measurements and accepted as a perpetuation of the original corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set standard marker in a monument box in the centerline of East and West road in place of sleigh shoe, as directed by the Peer Group in a regular meeting on June 5, 1996,.

Witnesses:

Corner is in centerline East and West road
Corner is 2' East of centerline North and South road.
48" Locust N.12°W. 61.66' to nail
48" Oak S.33°W. 43.67' to nail
27" Maple S.37°E. 43.15' to nail

Ratified by Peer Group in accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 2/3/97 *D.R.A.*



Signed by James E. Boynton Date 1-17-97
Surveyor's Michigan License No. 29239