

1993

SEP 23 8 37 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

County Remonumentation Program

For corners in Hamilton Township
Van Buren County (County)

Located In: Corner Code #

Mark A. Smith
VAN BUREN CO.
REGISTERED DEEDS

- 1. Public Land Survey N 1/4 post Section 4 T 4S R 15W F-1
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald R. Gilchrist in a field survey on _____, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No corner set by Government
N 1/4 post, Section 4, Hamilton Township, Town 4 South, Range 15 West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner set by Government
Set Harrison Marker on line and split of dist per Peer Group Meeting 7/28/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Harrison Marker ("Co. Sur.")
12" whitewood - S 40° E - 40.80 to Pk/W in E face
24" sugar - S 20° W - 47.42' to Pk/W in SW face
12" pop - East - 55.37+ to Pk/W in S face
14" syc - N 80° W - 23.79' to Pk/W in S. face
12' N of CL E & W Rd
Witness post 2' North

Signed by Donald R. Gilchrist
Surveyor's Michigan License No. R.L.S. 13583

Date 9/20/93

