

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in VAN BUREN

HAMILTON TWP COMMISSION

Located In:

Corner Code #

- 1. Public Land Survey SW corner Sec. 15 T4 S. R 15 W G-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Maule & Smith VAN BUREN CO. REGISTER OF DEEDS

DEC 1 11 57 AM '95

FILED 7 JAN 10 1996 1010 1010 1010

Register of Deeds Stamp & File Number

John C. Hunt, PS

August 7,

95

I, in a field survey on 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column G and row 7.

A. Description of original monument and accessories and/or subsequent restoration:

1/1830 - Government: E.H. Lytle, DS: North between Sec. 21 & 22 a distance of 80.00 chs. (5280') to Section corner. Corner is on a 10" White Oak. 4/22/1980 D.R. Pitts, PS: Sec. 16. Field note shows traverse between SW cor. & SE cor. P.Coulson fd. pipe at SE cor. Witnesses: NE cor. entrance, foundation of Hamilton Grange Hall, 91.15', Phone pole S45°E 65.10', 28" Oak N25°W 38.55'; corner is 6' +-West of centerline of North & South road in line with North edge of travel West & center line East. 5/29/1980: Recordation Certificate L.2 p.598: pipe, same witnesses as above. 10/27/1980 J.C. Hunt PS: Sec. 15. Used corner in survey. Distance from SW corner to NW corner is 5278.22'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 Southwest corner Section 15 T4S-R15W, Hamilton Twp., Van Buren Co. This corner common to Sec. 15, 16, 21, & 22. Found 1" iron pipe 6' West of centerline of CR 215, in line with centerline of 84th Ave. to East & 7' North of centerline of dirt trail to West. Removed & set Harrison Marker & mon box.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON JULY 5, 1995, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group in accordance with P.A. 345 of 1990 Van Buren County Surveyor

Date 5/5/95 D.P.B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 HARRISON MARKER IN MONUMENT BOX S36°W 90.98' NE corner entrance (foundation) to Hamilton Twp. Hall. S53°E 124.40' Set PK nail & washer in North face of pole. N28°W 37.82' Set PK nail & washer in East face of 33" Oak. N40°E 56.37' Set PK nail & washer in SW corner of RR tie post.



Lib 4 Page 324

Signed by John C. Hunt, PS

Date Nov. 27, 1995

Surveyor's Michigan License No. 23513