

VAN BUREN COUNTY REMONUMENTATION PROGRAM

1993

LIBER 4 PAGE 123 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 3 9 00 AM '94

For corners in

<u>Van Buren</u> (County)	Located In: <u>Hamilton Twp.</u>	Corner Code #/
1. Public Land Survey	Sec. 25 T 4 S. R 15 W.	K-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Mark A. Smith
VAN BUREN CO.
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John C. Hunt, PS, in a field survey on Dec. 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
K-10 1/1830 EH Lytle DS ran N. 40 ch & set 1/4 sec. post. He wit.: 28" Wht. Oak S52°W 183 lks., 12" Maple N19°W 52 lks. 5/4/1926 TA Smith CS fd. SW cor. of Sec. 25. He meas. N. 1311.4' to fence W. & cont. N. 1311.4' to 1/4 post; drove iron pipe in line of N. & S. fence West. He wit.: 12" soft Maple N70°E 5' to center line. Meas. S. 721.3', drove pipe on sec. line. Wit.: Cor. of square house N60°30'W 85.5'. Meas. W. to center 1/4 post 2635.0'. 6/8/1961 WQ Smith CS noted fd. 1/4 post, meas. N. 2611.50'. 5/29/1973 Fd. 1/2" pipe 6" above surface, witness stump remains, new witnesses. 6/5/1973 Used in survey rec. L.4 p.110. Recordation Certificate L.2 p.217.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-10 West quarter post of Sec. 25, T4S-R15W, Hamilton Twp.
Corner evidence found: 1/2" Iron Pipe 6" above surface in line with down fence & brush row South and West & also in line with down fence to North. Removed iron pipe & set Harrison Marker with Survey Marker Witness Post on East side.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON DEC. 8, 1993, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-10 HARRISON MARKER WITH SURVEY MARKER WITNESS POST ON EAST SIDE.

N15°E 10.40' Nail & tag in West face of 10"-12" double Maple
N20°W 14.30' Nail & tag in NE face of 11" Swamp Oak.
West 21.45' Nail & tag in South face 10" Maple tree.
North 23.31' Nail & tag in East face of twin 6" Maples.



Signed by John C. Hunt, P.S. Date Dec. 30, 1993
Surveyor's Michigan License No. 23513