

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 3 9 00 AM '94

LIBER 4 PAGE 124  
1993 COMMISSION

For corners in

Van Buren (County) Located In: Hamilton Twp. Corner Code #:

1. Public Land Survey Sec. 25 T4 S. R 15 W. K-11  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

Mark A. Smith  
VAN BUREN CO  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John C. Hunt, PS, in a field survey on Dec. 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1/1830 EH Lytle DS ran N. 80 ch & set post cor. in swamp; wit.: 6" Blk. Ash S10°E 36 lks, 8" Blk. Ash N.35°W 19 lks. Gov. ran E. 40 ch to 1/4 post & a total of 80 ch to town line. 1/4 Post is a 12" Blk. Ash. Gov. ran W. 79.90 ch & S. 80 ch. 4/23/1922 WH Goss CS: Pile of stones. Meas. W. 9.97 ch & cont. W. 9.97 ch & cont. W. 19.875 ch to 1/4 post for total of 2,627.79'. Sec. 35 N 1/4 post, pipe, 39.75 ch to sec. cor. Sec. 35 E 1/4 post is buggy axle. 5/4/1926 TA Smith CS fd. iron bar & stones around 3" below surface. Old Notes: some wit. Meas. N. 1311.4' to fence W. & 1311.4' to E 1/4 Post Sec. 26. Set iron pipe in line w/ fence for 1/4 post & set iron pipe 721.3' S. of 1/4 post. Meas. W. from cor. 1326.2' to fence N. Distance to 1/4 Post = 2625.0'. 1973 WQ Smith CS fd. old iron & stones down 24". Set iron rod to surface in C/L-C/L rds. Survey rec. L.4 p.110 & corner recordation Certificate in L.2 p.217.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-11 Southwest corner of Sec. 25, T4S-R15W, Hamilton Twp.  
Corner evidence found: 1/2" Iron Rod over 1" Iron Bar with small stones around it, approximately 2' down. Corner in line with centerline of roads to North & West. Removed irons and set Harrison Marker and survey marker Witness Post on East side.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON December 8, 1993, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 HARRISON MARKER WITH SURVEY MARKER WITNESS POST ON EAST SIDE.

- N85°W 22.27' South leg of sign post.
- N03°E 65.47' West leg of sign post.
- N75°E 7.59' Nail & tag in NW face of 5" dia. tree.
- S10°W 17.37' Nail & tag in East face of 5" dia. tree.



Signed by John C. Hunt, PS

Date Dec. 30, 1993

Surveyor's Michigan License No. 23513