

**SURVEY & REMONUMENTATION**

**FILED**

APR 25 1995

**VAN BUREN COUNTY REMONUMENTATION PROGRAM**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

DEC 20 9 58 AM '94

For corners in

VAN BUREN  
 (County)

Located In:  
Hamilton Twp.

Corner Code #

- |                         |                      |         |         |            |
|-------------------------|----------------------|---------|---------|------------|
| 1. Public Land Survey   | Sec. 13              | T4 S.   | R 15 W. | <u>L-5</u> |
|                         | N $\frac{1}{2}$ Post | T _____ | R _____ | _____      |
|                         |                      | T _____ | R _____ | _____      |
|                         |                      | T _____ | R _____ | _____      |
| 2. Property Controlling | S _____              | T _____ | R _____ | _____      |
| in Section              | S _____              | T _____ | R _____ | _____      |
| 3. Miscellaneous        | S _____              | T _____ | R _____ | _____      |
| Property in Sec.        | S _____              | T _____ | R _____ | _____      |
| 4. Lot No. _____        | Recorded Plat _____  |         |         |            |
| 5. Private Claims _____ | _____                |         |         |            |

*Mark A. Smith*  
 VAN BUREN CO.  
 REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

I, John C. Hunt, P.S., in a field survey on Dec. 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-5 1/30/1830 GOV.: EH Lytle DS, Set  $\frac{1}{4}$  post at 40.155 chs. 11/1871 AJ Pierce CS, Bk. 4 p.81: Stump of both wit. remain, stake by Blackman OK; Meas. W. 20.06 chs. to  $\frac{1}{8}$  post, cont. W. 1323.96' to NW cor., total 2647.92'. 5/3/1905 WH Goss CS: Bk. 1 p.198, fd. old stake, set stone, no suitable wit. near. Meas. E. 20 chs. to  $\frac{1}{8}$  post, cont. E. 20 chs. to NE cor.; Meas. W. 20.125 chs to  $\frac{1}{8}$  post, cont. W. 1328.25' to NW cor., total 2656.50'; Meas. S. 23.75 chs to C/L of road, cont. S. 16.25 chs. to Center  $\frac{1}{4}$  post, total 2640'. 5/27/1904 Field Bk.: Set Center  $\frac{1}{4}$  post midway bet. E&W  $\frac{1}{4}$  posts; then ran from N $\frac{1}{4}$  post S. thru Center to lake; Marked sycamore at lake w/ 3 notches on N & S sides. 9/10/1947 TA Smith CS: Drawing shows corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-5 Corner common to Sections 12 & 13 T4S-R15W, Hamilton Twp.  
 Corner evidence found: Found 1" iron pipe over pointed stone with notch mark on South side. Railroad tie corner post for fences North, East, & West. Removed 1" I.P. & stone & set Harrison Marker with Survey Marker Witness Post on North side.


THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON APRIL 13, 1994, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Ratified by Peer Group in accordance with P.A. 345 of 1990  
 Van Buren County Surveyor

Date 12/28/94 J. P. G.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-5 HARRISON MARKER  
 S.10°E. 2.08' Set PK nail & washer in SW face of 20" dia. dead tree.  
 N.85°W. 11.06' Set PK nail & washer in S. face of 18" Oak.  
 S.02°E. 57.06' Set PK nail & washer in W. face 18" Oak.  
 North 10.71' Set PK nail & washer in W. face railroad tie post.



Signed by John C. Hunt, P.S.  
 Surveyor's Michigan License No. 23513

Date Dec. 20, 1994

*Libel 4 page 254*