

SURVEY & REMONUMENTATION

JUN 14 1994

COMMISSION

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Van Buren (County) | Located In: Keeler Twp. | Corner Code # |
|---------------------------------------|---|---------------|
| 1. Public Land Survey | Sec. 33, T 4 S. R 16 W. S 1/2 Post T R | F-13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, John C. Hunt, P.S. in a field survey on March 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/1827 W. Brookfield DS set 1/2 post w/ Wit.: 5" White Oak N59°30'E 13 8.58', 5" White Oak N46°30'W 53 lks. 34.98'. Jog 48.51' at 1/2 post. 1941 Plat of Krohne's Peninsula 4-5-16 shows N 1/2 post (S 1/2 Post Sec. 33-4-16) as P.O.B. From lot cor. bet. Lots 70 & 71 to 1/2 post = 758.0'. 5/22/1952 WJ Smith CS. His drawing shows dist. from cor. bet. lots 70 & 71 of Krohne's Pen. to the S 1/2 post of Sec. 33 as 806.51', giving a jog of 48.51'. John JC Hunt PS had data that tied to Gov. Wit. tree (5" White Oak) which is now a 36" White Oak tree.

**Ratified by Peer Group in accordance with P.A. 345 of 1990
 Van Buren County Surveyor**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S 1/2 Post Sec. 33, T4S-R16W, Keeler Twp.

Found 1" Iron Pipe 36' South of centerline of road. Replaced with Harrison Marker & set survey sign post on South side.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Register's Office
 Van Buren Co., Mich. } *Filed 4/11 1994 8:59 o'clock A M*
Mark A. Smith per Register

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 HARRISON MARKER

North 66.00', 1/2" I.R. with cap #23513.
 0.7' South & 0.3' East of SE corner RR tie end post for fence North & West.
 S50°W, 25.70', NE corner garage.
 N80°E, 9.18', Set nail & tag in South face of 36" Oak.
 S10°E, 5.91', Set nail & tag in NE face of 5" dia. Pine.

Marked 14 June 1994

Signed by John C. Hunt, P.S. Date April 1, 1994

Surveyor's Michigan License No. 23513