

VAN BUREN COUNTY REMONUMENTATION PROGRAM

LIBER 4 PAGE 65  
1993  
COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Oct 19 11 52 AM '93

For corners in

|                                       |                            |                      |
|---------------------------------------|----------------------------|----------------------|
| <u>Van Buren</u><br>(County)          | Located In:<br>Keeler Twp. | Corner Code #<br>G-7 |
| 1. Public Land Survey Sec. 16         | T 4 S. R 16 W.             | G-7                  |
|                                       | T R                        |                      |
|                                       | T R                        |                      |
|                                       | T R                        |                      |
| 2. Property Controlling in Section    | S T R                      |                      |
|                                       | S T R                      |                      |
| 3. Miscellaneous Property in Sec.     | S T R                      |                      |
|                                       | S T R                      |                      |
| 4. Lot No. _____, Recorded Plat _____ |                            |                      |
| 5. Private Claims _____               |                            |                      |

Mark A. Smith  
VAN BUREN CO.  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, John C. Hunt, P.S., in a field survey on July 28, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
2/9/1830 Gov. Survey: EH Lytle DS: Set post cor. at 80.00 ch, 12" W. Oak N.26°E. 56 lks., 45" W. Oak E. 36 lks. 7/20/1868 CD Lawton CS: Worked on 1/4 cor. 11/1868 CD Lawton CS: "Compass laying off course & dist. from single wit. tree remaining. I dug & fd. good evidence of orig. stake, about 3' NW of stake set by Baxter--set stake & brick accordingly". 1869 AJ Pierce CE: Surveyed & platted Vill. of Keeler. Set long stone w/ cross on top. 1884 AA Fosdick CS: Wit.: 6" Sugar S.28°30'E. 80.25 lks., 8" Sugar N.36°E. 70.25 lks., Meas. W. 1314.55' & 1314.55' to N 1/4 post. 3/14/1933 TA Smith CS: Used in surveys in Sec. 21 & 22. 6/1/53 WQ Smith CS: Used in surveys in 1955, 1959, 1957, & 1967. 7/13/72 WQ Smith CS: Survey (L.2 p.160); Fd. brass marker in mon box rec. L.1 p.582. 5/4/73 Rec. L.2 p.61. 4/10/73 DR Gilchrist CS: Survey L.3 p.279, wit. as rec. above. 5/21/75 WQ Smith survey L.5 p.278. 11/9/78 RL Harner survey L.8 p.38, wit. rec. L.2 p.561

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 8/31/84 JC Hunt survey.

G-7 Section corner common to Sections 15, 16, 21, & 22, T4S-R16W, Keeler Twp. (Keeler Village). Corner evidence found: On July 28, 1993, found brass standard marker in monument box in C/L-C/L of roads as filed in L.2 p.561 & as per survey rec. in L.9 p.71-73. No Harrison Marker set.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS AT A MEETING HELD ON MAY 26, 1993, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-7 STANDARD BRASS MARKER IN MONUMENT BOX

- N.45°W. 37.80' PK nail in NE face of pole.
- S.45°E. 53.55' PK nail in N. face of pole.
- N.30°E. 70.62' PK nail in W. face of 15" dia. Elm.
- S.30°W. 48.60' PK nail in NE cor. 6" wood post near NE cor. of store.

Signed by John C. Hunt  
Surveyor's Michigan License No. 23513

Date Oct. 17, 1993

