

DEC 28 2 24 PM '94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KEELER TWP.
VAN BUREN
(County)

Located In: Corner Code #

Mark A. Smith
VAN BUREN CO
REGISTERED SURVEYOR

- 1. Public Land Survey T-4S R-16W L-13
S 1/4 COR SEC-36 T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ADDRESS, in a field survey on DECEMBER 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

3/1827 - GOVERNMENT - WILLIAM BROOKFIELD, D.S.
WEST ON SOUTH BOUNDARY OF SECTION 36 A DISTANCE OF 40.00 CHS (2640.00')
SET 1/4 SECTION POST.
WITNESSES: 9" W. OAK N 40DEG-20' E 11 LKS (7.26')
7" W. OAK N 36DEG W 51 LKS (22.21')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. BRICK IN C/L OF OLD ROAD BED

OLD "I" BEAM FENCE COR POST EAST-6'+/-, SOUTH 25'+/-
DIST TO SW COR SEC-36 2634.24'
DIST TO SE COR SEC-36 2660.83'

Ratified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12/28/94 D. R. G.

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS GOVERNMENT MONUMENT WAS RESTORED WITH THE APPROVAL OF THE VAN BUREN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS. 12-21-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED BRICK WITH HARRISON MONUMENT.

PK & TAG NW SDE 32" CHERRY S 10 W 23.99'
PK & TAG E SDE 8" HICKORY N 10 W 12.15'
PK & TAG NW SDE TWIN CHERRY (20"-22") S 50 W 62.10'
PK & TAG NE SDE 10" ASH S 45 E 13.99'
NE COR 6" "I" BEAM FE COR POST S 15 E 25.65'
IN C/L OF OLD ROAD BED



Signed by *Basil Address* Date 26 DEC 94
Surveyor's Michigan License No. 30075 9536 12/28 0104 1993

Label 4 page 261