SURVEY & REMONUMENTATION

FEB 23 1994

COMMISSION

RC 1201

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

27003 PA 579

For corners in WAYNE (County)

	Located In:	Corner Code ##
1. Public Land Survey	T 1 S R 8 E	A 1
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. ___, Recorded Plat ___
5. Private Claims ___



I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSESS REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:
WAYNE CO. RD. COMM INVENTORY OF GOV'T CORNERS PRIOR TO TAKEOVER FROM TOWNSHIPS
"X" IN PAVEMENT (SET BY CERA)
NW 55.37' USC & GS MONUMENT (NOT RECOVERED)
NE 39.76' "X" IN CULVERT (GONE)
SE 81.14' 30" ELM (GONE)
SE 40.22' "X" IN CULVERT (GONE)
SW 52.05' 12" WILD CHERRY (GONE)
W 84.75' 28" WALNUT (CERA 1935) (MEAS 84.90')
NW 48.23' 8" WALNUT (CERA 1935) (MEAS 47.87')

1972 LIBER 18060, PG 601
MONUMENT IN BOX IN ASPHALT A "X" EIGHT MILE & NAPIER RD
NW 46.99' BRASS TAG IN DEL POLE (MEAS 46.90')
NE 46.13' BRASS TAG IN MBT POLE (GONE)
SE 66.27' SPIKE IN MBT POLE (MEAS 66.31')
SW 57.41' SPIKE IN 6" TREE (MEAS 57.37')

NOTE: TWO 1930 BUREAU OF TAXATION WITNESS REMAIN
WLY 84.70' 28" WALNUT (MEAS 84.90')
NW 48.96' 8" ASH (MEAS 47.87')

WAYNE CO. RD. COMM WITNESSESS 1970 MONUMENT IN BOX
NE 46.19' P.K. IN P. POLE (GONE)
SE 66.35' MBT POLE (MEAS 66.31')
SW 57.48' 4" ASH (MEAS 57.37')
NW 47.50' D.E. POLE (MEAS 47.50')
NW 48.96' 18" ASH (MEAS 47.87')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT IN MONUMENT BOX (RAISED BOX TO ROAD SURFACE)
S 30° E 66.31' SET NAIL & TAG IN E. SIDE MBT POLE (PREVIOUS WITNESS)
S 15° W 57.37' SET NAIL & TAG IN E. SIDE 12" ASH (PREVIOUS WITNESS)
N 35° W 46.90' SET NAIL & TAG IN D.E. POLE (PREVIOUS WITNESS)
N 20° W 47.87' SET NAIL & TAG E. SIDE 21" ASH (PREVIOUS WITNESS)
N 55° W 84.90' SET NAIL & TAG IN 52" WALNUT (PREVIOUS WITNESS)

DISTANCE TO A 2 MEASURED AS 2322.41' RECORDED IN 1930 AS 2322.31'
DISTANCE TO B 1 MEASURED AS 2695.46' RECORDED IN 1930 AS 2695.75'
SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

STATE OF MICHIGAN
PAUL V. SCHWIMMER
No. 24618
REGISTERED LAND SURVEYOR

Signed by Paul V. Schwimmer Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

2R
11KD