

FEB 28 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1127003 PA 580

For corners in

WAYNE (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>1 S</u> R <u>8 E</u>	<u>A 3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

93 DEC -3 AM 9:54
RC 1202
REGISTER OF DEEDS
MICHIGAN
LANSING, MI

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: PREVIOUSLY RECORDED IN:

1972 LIBER 18060, PG 601
MONUMENT IN BOX IN ASPHALT AT 'X' OF SEVEN MILE AND NAPIER RDS
NW 59.02' SPIKE IN MBT POLE (GONE)
NE 75.91' BRASS TAG IN 24" TREE (MEAS 75.55')
SE 47.60' WAYNE COUNTY BENCHMARK (DESTROYED)
SW 77.82 BRASS TAG IN 4" POST (GONE)

NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN

WAYNE COUNTY ROAD COMMISSION WITNESSES 1970 MONUMENT IN BOX

1981 LIBER 21259, PG 950
FOUND CONC. MONUMENT IN BOX
N 30° E 75.46' NAIL IN 24" SUGAR MAPLE (MEAS 75.55')
S 60° E 62.05' NAIL IN W. FACE D.E. POLE (MEAS 62.05')
S 30° E 97.38' NAIL IN W. FACE MBT POLE (MEAS 97.38')
N 60° W 58.07' NAIL IN E. FACE MBT POLE (MEAS 58.07')

NE 75.92' 23" MAPLE (MEAS 75.55')
SE 62.24' D.E. POLE (MEAS 62.05')
NW 59.04' MBT POLE (GONE)

SUBSEQUENT WITNESSES BY ROSKELLY IN ACT 132 SURVEY No. 81-9-68 SAME AS 1981

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT IN MONUMENT BOX IN ASPHALT ROAD
N 30° E 75.55' SET NAIL & TAG W. SIDE 24" MAPLE (PREVIOUS WITNESS)
S 65° E 209.65' N.W. CORNER 2 STORY BLOCK BUILDING
S 60° E 62.05' FOUND NAIL IN W. FACE D.E. POLE (PREVIOUS WITNESS)
S 30° E 75.00' SET NAIL & TAG IN W. FACE 12" MAPLE
S 25° E 97.38' FOUND NAIL W. FACE OF D.E. POLE (PREVIOUS WITNESS)
S 75° W 116.55' SET NAIL & TAG IN N. SIDE 8" PINE
N 60° W 58.07' FOUND NAIL IN E. FACE MBT POLE (PREVIOUS WITNESS)

DISTANCE TO B 3 MEASURED AS 2720.75' RECORDED IN 1930 AS 2720.96'
DISTANCE TO A 4 MEASURED IN 1986 AS 2645.51' RECORDED IN 1930 AS 2646.24'
SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer

Date NOVEMBER 16, 1993

Surveyor's Michigan License No. 24618

2R
UKD