

**SURVEY & REMONUMENTATION**

FEB 28 1994

**RC 1203**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| WAYNE<br>(County)                     | Located In:               | Corner Code # |
|---------------------------------------|---------------------------|---------------|
| 1. Public Land Survey                 | T <u>1</u> S R <u>8</u> E | <u>A 7</u>    |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |
| 5. Private Claims _____               |                           |               |

LI 27003 PA 581

99 DEC -3 AM 8:54  
 REGISTERED LAND SURVEYORS  
 MICHIGAN  
 10000

Register of Deeds Stamp & File Number

I, **PAUL V. SCHWIMMER**, in a field survey on **NOVEMBER 1**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:  
 1972 LIBER 18145, PG 269  
 CONCRETE MON IN BOX A "X" NAPIER & FIVE MILE ROAD, 1' DEEP  
 NE 67.55' BRASS TAG IN D.E. POLE (MEAS 68.77')  
 SE 71.12' USGS BENCH MARK MONUMENT, SW 161.12' D.E. POLE (MEAS 161.78'), NW 63.72' 3' ELM (GONE)

NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN

1975 LIBER 19026, PG 906  
 CONCRETE MONUMENT IN BOX  
 NE 68.60' SPIKE IN SE SIDE D.E. POLE (MEAS 68.77')  
 NE 59.50' SW FACE OF SIGN POST (GONE 1993)  
 SE 71.10' CENTER OF BRASS PLUG USGS BENCHMARK (GONE 1993)  
 SW 67.70' "X" CUT IN TOP OF CONCRETE POST (MEAS 68.18)

WAYNE COUNTY RD. COMMISSION 1975  
 FOUND MONUMENT IN MON. BOX  
 NE 68.60' DE POLE (MEAS 68.77')  
 NE 59.50' SIGN POST (GONE)  
 SE 71.10' USGS BM (NOT RECOVERED)  
 SW 67.70' "X" IN CONC. POST (MEAS 68.18)

1975 LIBER 19080, PG 299  
 FOUND MON. IN BOX FROM W.C.R.C. WITNESSES DATED 4-1-1970  
 N 35°E 67.97' NAIL W. FACE D.E. POLE (DOES NOT MATCH ABOVE OR NEW TIE DISTANCES)  
 S 55°E 71.14' USGS MARKER (NOT RECOVERED 1993)  
 S 30° E 93.35' NAIL W. FACE 15" CHERRY (MEAS 92.99')  
 S 25° W 86.75' NAIL E. FACE WOOD POST (MEAS 86.52')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONC. MONUMENT IN MONUMENT BOX

S 15° E 92.99' SET NAIL & TAG E. FACE 20" CHERRY (PREVIOUS WITNESS)  
 S 25° W 127.72' SET NAIL & TAG W. FACE 8" BOX ELDER  
 S 70° W 161.78' SET NAIL & TAG N.W. FACE POWER POLE  
 N 45° E 68.77' SET NAIL & TAG S.E. FACE POWER POLE (PREVIOUS WITNESS)  
 S 25° W 86.52' NAIL E. FACE WOOD POST (PREVIOUS WITNESS)  
 SW 68.18' "X" IN TOP OF CONCRETE POST (PREVIOUS WITNESS)

DISTANCE TO A 6 MEASURED AS 2632.31' RECORDED IN 1930 AS 2632.96'  
 DISTANCE TO B 7 MEASURED AS 2726.59' RECORDED IN 1930 AS 2726.51'  
 SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer

Date NOVEMBER 3, 1993

Surveyor's Michigan License No. 24618

2R  
11KD