

**SURVEY &
REMONUMENTATION**

RC 1542

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

WAYNE (County) ASHTON Located in: _____ Corner Code # _____

1. Public Land Survey	T	<u>1</u> S	<u>R</u> 8 E	<u>A-13</u>
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property controlling in Section	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____
	S	_____	T	_____
4. Lot No. _____, Recorded Plot _____				
5. Private Claims _____				

L127800PA023

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-21-94 *DBJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, PAUL V. SCHWIMMER, in a field survey on DECEMBER 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L
1											
2											
3											
4											
5											
6											
7											
8											
9											
10											
11											
12											
13											

A. Description of original monument and accessories and/or subsequent restoration:
 ORIG. GOVERNMENT NOTES 1815, WITNESSED BY BALESS JIMMINGS - SET POST (1)
 SUGAR MAPLE 12' N11°E 46 LINKS (2)
 SUGAR MAPLE 6' S88°W 32 LINKS (3)
 WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (4)
 N.W. 73.30 U.S.C. & G.S. B.M. #250 (5)
 N.E. 38.13 'X' ON SIGN POST (6)
 S.E. 74.85 ILLEGIBLE (7)
 S.W. 92.65 4' HICKORY (8)
 N.W. 113.48 1' ELM. (9)
 FOUND IN W.C.R.C. GRID BOOK BY K. MADISON IN 1933 FND IRON PIPE (10)
 N25°W 73.35 U.S.G.S. B.M. (5)
 BOARD OF WAYNE CO. RD. COMM IRON IN BOX FOUND IN 1970 (10)
 N.E. 40.27 'X' IN WCR SIGN (11)
 S.W. 92.94 21' HICKORY (8)
 N.W. 75.87 BELL POLE (12)
 N.W. 54.54 'X' IN CONC. MARKER (13)

RC 1542

CONTINUED ON BACK

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
 A-13 IN ADDITION TO OUR RESEARCH EFFORTS, WE OBTAINED THE RESULTS OF THE WASHTENAW COUNTY REMONUMENTATION WORK.
 BASED ON THE COMBINED EFFORTS, WE ARE ACCEPTING THIS LOCATION AS THAT OF A-13

\$ 16.00 MISCELLANEOUS RECORDING
 28 DEC 94 8:15 A.M. RECEIPT# 4A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-13 FOUND 5/8' IRON IN A MONUMENT BOX 0.85 BELOW THE ROAD SURFACE. THE IRON WAS CAPPED WITH A WASHTENAW COUNTY REMONUMENTATION CAP
 N29°E 62.22 FOUND 'X' ON W. SIDE WATER GATE VALVE MANHOLE
 N29°E 61.54 FOUND 'X' ON S. SIDE WATER GATE VALVE MANHOLE (22)
 N30°E 64.88 FOUND 'X' ON TOP OF D.W.S.D. STEEL MARKER
 S25°E 68.23 FOUND 'X' ON TOP OF D.W.S.D. STEEL MARKER
 S35°E 81.84 CORNER OF 6' HIGH STEEL FENCE POST (18)
 S40°W 63.98 NAIL W/ W.C.R.C. TAG IN DE. POLE
 S39°W 52.06 BASE OF ROAD NAME SIGN (19)
 N63°W 102.11 NAIL W/ WASH. CO. REMON TAG IN 12' ASH (20)
 N42°W 77.55 FD. P.K. IN S. SIDE 10" MAPLE
 N12°W 162.69 NAIL W/ WASH. CO. REMON. TAG IN 12' ASH (21)



*2 R
14 D
MISC*

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
 Surveyor's Michigan License No. 24618

Date 12-21-94