

FEB 28 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>8 E</u>	<u>B 3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LI 27003 PA 582

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:
1972 LIBER 18060, PG 605
MONUMENT IN BOX IN ASPHALT ON SEVEN MILE
NW 52.45' SPIKE IN 12" TREE (MEAS 52.40')
NE 38.98' SPIKE IN 15" TREE (MEAS 39.00')
S 38.56' CONS. POWER MARKER (MEAS 38.80')
SW 38.56' SPIKE IN 15" TREE (GONE)

NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN

WAYNE COUNTY ROAD COMMISSION WITNESSES 1970
MONUMENT IN BOX
NE 29.64' MBT POLE (MEAS 29.60')
SE 73.53' 14" MAPLE (GONE)
SW 38.60' 14" MAPLE (GONE)
NW 52.48' 15" MAPLE (MEAS 52.40')
N 29.64' MBT POLE (MEAS 29.60')

1976 ROSKELLY SURVEY No. 76-7-116
FD. IRON IN BOX
SE 50.04' NAIL IN 10" CHINESE ELM (MEAS 50.10')
NW 52.52' NAIL IN 18" SUGAR MAPLE (MEAS 52.40')
N 29.65' NAIL IN MBT POLE (MEAS 29.60')
NE 38.86' NAIL IN 16" SUGAR MAPLE (MEAS 39.00')

SUBSEQUENT SURVEYS AND ACT 74 BY ROSKELLY FROM 1976 TO 1986 RELY ON THE IDENTICAL ABOVE WITNESSES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 5/8" IRON IN BOX 0.75' BELOW ASPHALT SURFACE,
RAISED MONUMENT BOX
N 05° E 29.60' SET NAIL & TAG E SIDE MBT POLE (PREVIOUS WITNESS)
N 35° E 39.00' FD NAIL IN E. SIDE BADLY DAMAGED 15" MAPLE (PREVIOUS WITNESS)
S 35° E 50.10' SET NAIL & TAG W. SIDE 12" CHINESE ELM (PREVIOUS WITNESS)
S 05° E 38.80' CENTERLINE OF GAS PIPELINE MARKER (PREVIOUS WITNESS)
N 45° W 94.48' SET NAIL & TAG IN S. SIDE 15" MAPLE
N 15° W 52.40' FD NAIL E. SIDE 18" MAPLE, RESET WITH TAG (PREVIOUS WITNESS)

DISTANCE TO C 3 MEASURED AS 2646.09' RECORDED IN 1930 AS 2647.27'
DISTANCE TO A 3 MEASURED AS 2720.75" RECORDED IN 1930 AS 2720.34"
SET REMONUMENTATION DISC AND CAP ON FOUND IRON

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer

Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618



2R
11KD