

FEB 28 1994

RC 1206

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LI 27003 PA 584

REGISTER OF DEEDS  
MICHIGAN STATE BOARD OF LAND SURVEYORS

99 OCT -3 AM 9:54

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S R 8 E</u>	<u>B 11</u>
	T _____	_____
	T _____	_____
	T _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

I, PAUL V. SCHWIMMER, in a field survey on OCTOBER 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:  
WAYNE COUNTY ROAD COMMISSION WITNESSES 1970 - MONUMENT  
NE 37.50' UNDERGROUND CABLE MARKER (TRANSFERRED TO ACCOMPANYING POLE & MEAS 37.02')  
SE 61.82' MBT POLE (MEAS 61.67')  
SLY 33.03' MONUMENT (MEAS 33.05')  
SW 25.06' 15' MAPLE (GONE)

1978 LIBER 20176, PG 603 - 3/4" IRON IN CONCRETE  
SLY 32.97' MONUMENT (MEAS 33.05')  
N 20° E 36.98' NAIL IN E. SIDE P.P. (MEAS 37.02')  
S 30° W 25.13' MSHD TAG IN 14' MAPLE (GONE)

NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN

1980 ACT 132 SURVEY - FOUND CONC. MONUMENT  
N 30° E 36.98' NAIL IN D.E. POLE (MEAS 37.02')  
S 70° E 61.64' NAIL IN MBT POLE (MEAS 61.67')  
SLY 33.04' CONCRETE MONUMENT (MEAS 33.05')  
S 05° W 23.69' NAIL IN MBT POLE (MEAS 23.71')  
S 30° W 25.10' NAIL IN 12' MAPLE (GONE)

1990 ACT 132 SURVEY  
FOUND CONCRETE MONUMENT  
N 30° E 37.00' NAIL IN D.E. POLE (MEAS 37.02')  
S 70° E 61.67' NAIL IN MBT POLE (MEAS 61.67')  
S 20° E 49.98' FIRE HYDRANT (MEAS 49.91')  
SLY 23.70' NAIL IN MBT POLE (MEAS 23.71')  
N 70° W 108.97' NAIL IN D.E. POLE (MEAS 108.98')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT, LOWERED TO 0.6' BELOW ROAD SURFACE  
N 35° E 37.02' SET NAIL & TAG IN S.E. FACE P. POLE (PREVIOUS WITNESS)  
S 15° E 49.91' CENTER OF FIRE HYDRANT (PREVIOUS WITNESS)  
SLY 33.05' FOUND CONCRETE MONUMENT (PREVIOUS WITNESS)  
S 05° W 23.71' SET NAIL & TAG IN W. FACE GUY POLE (PREVIOUS WITNESS)  
N 65° W 108.98' SET NAIL & TAG IN N.E. FACE P. POLE (PREVIOUS WITNESS)  
N 25° W 82.95' SET NAIL & TAG IN E. FACE 30' MAPLE  
S 65° E 61.67' SET NAIL & TAG IN N.E. FACE UTIL. POLE (PREVIOUS WITNESS)

DISTANCE TO A 11 MEASURED AS 2709.88' RECORDED IN 1930 AS 2709.73'  
DISTANCE TO C 11 MEASURED AS 2642.13' RECORDED IN 1930 AS 2642.50'  
SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618

2R  
11KD

