

FEB 28 1994

RC 1207

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>1 S</u> R <u>8 E</u>	<u>C 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

27003-585  
 REGISTER OF DEEDS  
 FOREST COUNTY REGISTER OF DEEDS  
 93 DEC -3 AM 8:51

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	D	E	F	G	H	I	J
2	6	5	4	3	2	1			
3									
4	7	8	9	10	11	12			
5									
6	18	17	16	15	14	13			
7									
8	10	20	21	22	23	24			
9									
10	30	29	28	27	26	25			
11									
12	31	32	33	34	35	36			
13									

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:  
 WAYNE COUNTY ROAD COMM. INVENTORY OF CORNERS PRIOR TO TAKE OVER OF TOWNSHIP ROADS  
 PLACED CONC. MONUMENT 11" DOWN

- N 85°53' W 33.14' MONUMENT (MEAS 33.10')
- S 47°43' W 45.47' MONUMENT (GONE)
- N 47°43' E 45.47' MONUMENT (MEAS 45.47')
- N 62°54' E 68.94' SPIKE IN 5' ELM (GONE)
- S 03°38' W 33.31' SPIKE IN 27' MAPLE (GONE)
- N 76°10' W 124.71' SPIKE IN 10' LOCUST (GONE)

NOTE: ONE 1930 BUREAU OF TAXATION WITNESS REMAINS  
 WLY 33.12' IRON (MEAS 33.10')

- 1972 LIBER 18060, PG 605 MONUMENT IN BOX IN ASPHALT
- NW 101.47' BRASS TAG IN FENCE POST (DESTROYED)
- N 32.74' BRASS TAG IN D.E. POLE (GONE)
- SE 70.03' BRASS TAG IN FENCE POST (GONE)
- SW 81.53' BRASS TAG IN D.E. POLE (GONE)
- W 33.2' WCRC MONUMENT IN EIGHT MILE RD (MEAS 33.10')

- WAYNE COUNTY ROAD COMMISSION WITNESSES 1970 MONUMENT IN BOX
- N 33.60' D.E. POLE (GONE)
- SW 82.01' D.E. POLE (GONE)
- SW 92.58' 6" ASH (MEAS 92.85')
- W 33.12' CONC. MON @ S.W. COR SEC 32 (MEAS 33.10')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- FOUND CONCRETE MONUMENT IN BOX IN ASPHALT
- NLY 36.30' FOUND NAIL IN D.E. POLE
- N 45° E 45.47' FOUND DAMAGED CONC. MONUMENT (PREVIOUS WITNESS)
- S 60° E 63.81' SET NAIL & TAG IN N SIDE 20' TWIN LOCUST
- S 65° W 92.85' SET NAIL & TAG IN S SIDE 14' MAPLE (PREVIOUS WITNESS)
- WLY 33.10' FOUND 1/2" ROD IN MONUMENT BOX (PREVIOUS WITNESS)
- N 75° W 194.30' SET NAIL & TAG S. SIDE 20' MAPLE

DISTANCE TO B 1 MEASURED AS 2668.38' RECORDED IN 1930 AS 2668.34'  
 DISTANCE TO D 1 MEASURED AS 2621.75' RECORDED IN 1930 AS 2621.50'  
 SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer Date NOVEMBER 16, 1993

Surveyor's Michigan License No. 24618



2R  
 11KD