

FEB 28 1994

LI 27003 PA 587

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 1 S R 8 E C 11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A black dot is present in cell B11.

I, PAUL V. SCHWIMMER, in a field survey on OCTOBER 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

FOREST & WANGEL OOD
REGISTERED DEEDS
ALLEN COUNTY, OHIO
DEC - 3 AM 8:54

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: PREVIOUSLY RECORDED IN:

- 1972 LIBER 18279, PG 155 FOUND MONUMENT
N 45° W 61.5' POWER POLE (GONE)
N 12° W 68.9' BURIED CABLE MARKER (GONE)
N 45° E 70.6' BURIED CABLE MARKER (GONE)
S 45° E 42.8' TELEPHONE POLE (GONE)
S 45° W 31.8' 'X' IN ROCK (GONE)
N 51° W 44.9' MONUMENT
1980 ACT 132 SURVEY No. 80-4-4 BY ROSKELLY FOUND 1/2" IRON BAR
S 60° E 73.55' R.R. SPIKE IN D.E. POLE (MEAS 73.60')
S 70° W 111.25' NAIL IN MBT POLE (MEAS 111.65')
N 45° W 49.87' SPIKE IN D.E. POLE (MEAS 49.90')
N 35° W 61.45' NAIL IN MBT POLE (GONE)

- NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN
WAYNE COUNTY ROAD COMMISSION WITNESSES 1973 IRON
ENE 76.11' 24° STUMP (GONE)
SE 42.70' GUY POLE (GONE)
SW 31.46' 'X' IN LARGE STONE (GONE)
NW 44.97' MONUMENT (GONE)
NW 61.38' D.E. POLE (GONE)
1992 LIBER 25888, PG 092 FOUND 3/4" IRON
NW 50.01' NAIL IN NE FACE P. POLE (MEAS 49.90')
SE 73.68' NAIL IN SW FACE P. POLE (MEAS 73.60')
WNW 143.82' NAIL IN S. FACE P. POLE (MEAS 143.78')
ESE 94.88' NAIL IN N. FACE 10" CHERRY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- FOUND 3/4" IRON PIPE IN MONUMENT BOX, RAISED WITH 1/2" STEEL ROD WITH DISC
N 80° E 143.78' SET NAIL & TAG S.E. SIDE P. POLE (PREVIOUS WITNESS)
S 45° E 73.60' SET NAIL & TAG S.W. SIDE P. POLE (PREVIOUS WITNESS)
S 85° W 111.65' SET NAIL & TAG N. SIDE UTIL. POLE (PREVIOUS WITNESS)
N 40° W 49.90' SET NAIL & TAG N.E. SIDE P. POLE (PREVIOUS WITNESS)
S 60° E 109.31' CENTERLINE OF FIRE HYDRANT
S 70° E 94.88' FOUND NAIL IN N. FACE 10" CHERRY (PREVIOUS WITNESS)

DISTANCE TO B 11 MEASURED AS 2642.13' RECORDED IN 1930 AS 2642.50'
DISTANCE TO C 10 MEASURED AS 2647.48' RECORDED IN 1930 AS 2647.66'
SET REMONUMENTATION DISC AND CAP ON IRON

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer

Date NOVEMBER 17, 1993

Surveyor's Michigan License No. 24618



2R
11K7D