

FEB 23 1994

RC 1210

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

27003 PA 588

93 DEC -3 AM 8:54
FOREST COUNTY BOARD OF RECORDS
MICHIGAN

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 8 E C 12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 12, column C.

I, PAUL V. SCHWIMMER, in a field survey on OCTOBER 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: PREVIOUSLY RECORDED IN:

1973 LIBER 18605, PG 69
MONUMENT
N 80° W 33.63' NAIL IN N SIDE U. POLE (MEAS 33.30')
WEST 32.85' MONUMENT (MEAS 32.56')
EAST 26.60' 4" OAK (GONE)
N 40° E 74.20' TRIPLE WILLOW (GONE)

FOUND STEEL CASED MONUMENT (BENT) 0.2' BELOW ROAD SURFACE. STRAIGHTED AND LOWERED TO 0.6' BELOW GRAVEL ROAD SURFACE

NOTE: NO 1930 BUREAU OF TAXATION WITNESS REMAIN

WAYNE CO. RD. COMM WITNESSES 1970
MONUMENT IN BOX
NE 59.99' CLUMP OF WILLOW (GONE)
SW 55.16' FENCE POST (GONE)
W 32.88' MONUMENT (MEAS 32.56')
NW 33.66' D.E. POLE (MEAS 33.30')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STEEL CASED MONUMENT WITH 5/8" STEEL BAR
S 80° E 52.23' SET NAIL & TAG IN N. FACE P. POLE
S 70° W 79.49' SET NAIL & TAG IN N.W. FACE 24" HICKORY
N 90° W 32.56' FOUND CONC. MONUMENT (PREVIOUS WITNESS)
N 80° W 33.60' SET NAIL & TAG IN N SIDE D.E. POLE (PREVIOUS WITNESS)

DISTANCE TO C 13 MEASURED AS 2635.12' RECORDED IN 1930 AS 2635.27'
DISTANCE TO C 11 MEASURED AS 2632.71' RECORDED IN 1930 AS 2633.13'
SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer

Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618

Handwritten initials: 2R 11K7