

SURVEYOR
RECORDED

FEB 28 1994

RC 1211

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 27003 PA 589

For corners in

WAYNE

(County)

Located In:

Corner Code -#

- 1. Public Land Survey T 1 S R 8 E C 13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

RECORDED
DEC 3 AM 8:54
MICHIGAN STATE BOARD OF LAND SURVEYORS

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL V. SCHWIMMER, in a field survey on OCTOBER 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. DESCRIPTION OF CORNER EVIDENCE . . .

WAYNE CO. RD. COMM INVENTORY OF CORNERS PRIOR TO ACCEPTANCE OF ROADS FROM TOWNSHIPS
 S 19° W 49.54' 36" WALNUT (GONE)
 N 16° E 74.59' NAIL E. SIDE 6' MAPLE (MEAS 74.51')
 N 64° W 76.54' NAIL S. SIDE 15' BOXELDER (GONE)
 N 46° W 93.18' SE CORNER BRICK FOUNDATION (MEAS 90.0')
 WLY 89.76' SECTION CORNER (MEAS 89.85')
 SLY 33.00' MONUMENT (MEAS 32.80')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:
 1973 LIBER 18605, PG 69
 1/2" IRON
 N 85° E 61.45' NAIL IN E. SIDE 5-10" OAKS (GONE)
 N 35° E 44.38' NAIL IN 21" ASH (MEAS 44.38')
 S 35° E 49.00' NAIL IN E SIDE 12" OAK (MEAS 48.93')
 WLY 89.82' 1/2" IRON AT SECTION CORNER (MEAS 89.85')

1930 BUREAU OF TAXATION WITNESSES MONUMENT
 NE 74.59' 8" MAPLE (MEAS 74.51')
 S 33.00' MONUMENT (MEAS 32.86 TO IP)
 SW 49.52' 36" WALNUT (GONE)
 W 89.36' MONUMENT (MEAS 89.36')
 NW 93.23' SCHOOL (MEAS 90.0 TO FOUNDATION)

1989 ACT 132 SURVEY
 FOUND 1/2" IRON PIPE
 N 10° E 74.22' 18" SUGAR MAPLE (MEAS 74.51')
 N 20° E 47.55' BENCH MARK 10-60 (MEAS 47.67')
 N 30° E 43.80' 18" TWIN ASH (MEAS 44.38')
 S 60° E 71.21' MBT POLE (MEAS 71.15')
 S 35° E 49.00' 12" BL. WALNUT (MEAS 48.93')
 N 20° W 127.81' D.E. POLE (GONE)
 WLY 89.84' NW. CORNER SECTION 5 (MEAS 89.85')

WAYNE CO. RD. COMM WITNESSES 1970 IRON
 NE 74.76' 18" MAPLE (MEAS 74.51')
 NE 43.83' 24" ASH (MEAS 44.38')
 SE 49.02' 11" WALNUT (MEAS 48.93')
 WLY 89.86' BRASS PLUG IN MON (MEAS 89.85')
 SE 71.23' P. POLE ADDED IN 88' (MEAS 71.15')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 5/8" REBAR IN GRAVEL ROAD
 N 20° E 74.51' SET NAIL & TAG IN W. FACE 20" MAPLE (PREVIOUS WITNESS)
 N 30° E 47.67' FOUND CONC. MONUMENT WITH BRASS DISC "WCRC BM" (PREVIOUS WITNESS)
 N 35° E 44.67' SET NAIL & TAG IN N.W. SIDE 28" TWIN ASH (PREVIOUS WITNESS)
 S 55° E 71.15' SET NAIL & TAG IN N.E. SIDE UTIL. POLE (PREVIOUS WITNESS)
 S 30° E 48.93' SET NAIL & TAG IN N.E. SIDE 12" WALNUT (PREVIOUS WITNESS)
 S 75° W 130.89' SET NAIL & TAG IN S.E. SIDE POWER POLE
 WLY 89.85' N.W. CORNER SECTION 5 FOUND IRON (PREVIOUS WITNESS)
 N 46° W 90.0' REMAINS OF CONCRETE FOUNDATION (PREVIOUS WITNESS)
 SLY 32.80' FOUND 3/4" BENT IRON PIPE (PREVIOUS WITNESS)

DISTANCE TO D 13 MEASURED AS 2647.24' RECORDED IN 1930 AS 2647.18'
 SET REMONUMENTATION DISC AND CAP
 THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer

Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618

2R
11KD