

**SURVEY &
REMONUMENTATION**

RC 1546

APR 25 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

L127800PA031

For corners in

WAYNE
(County)

Located In:

Corner Code #

- | | | | | |
|---------------------------------------|---|------------|--------------|-------------|
| 1. Public Land Survey | T | <u>1 S</u> | <u>R 8 E</u> | <u>E-13</u> |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| 2. Property controlling in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous Property in Sec. | S | T | R | |
| | S | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | |
| 5. Private Claims _____ | | | | |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-21-94
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, PAUL V. SCHWIMMER, in a field survey on DECEMBER 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1815, WITNESSED BY BALES JIMMINGS - SET POST (1)	WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (4)	ACT 74 SURVEY L18112 PA77
BEECH 12' S55°E 3 LINKS (2)	N.E. 44.05 6' CHERRY (5)	FND MONUMENT BY RAPHAEL LANDI IN 1972 (4)
IRONWOOD 6' N11°W 22 LINKS (3)	S.E. 46.70 MONUMENT (6)	N49°E 72.35 CENTER OF M.H. (11)
	S.W. 76.00 TEL POLE (7)	N26°W 38.78 NAIL IN UTIL POLE
	S.W. 33.22 TEL MANHOLE (8)	S51°W 33.78 CENTER OF MBT M.H.
	N.W. 46.70 MONUMENT (9)	S48°E 43.82 NAIL IN TEL POLE
	N.W. 36.65 TEL POLE (10)	

CONTINUED ON BACK

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

E-13 THIS CORNER TRACKS WELL WITH A NUMBER OF WITNESSES TRACING BACK TO THE 1930 INFORMATION. DISTANCE CHECKS TO E-12 AND F-13 CHECK VERY WELL.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 FOUND 1 1/2" IRON PIPE IN A MONUMENT BOX. TOP OF IRON IS 0.85' BELOW ROAD SURFACE
 N25°E 92.64 TOP SPINDLE OF HYDRANT
 N55°E 72.27 PUNCH MARK IN C/L MANHOLE (11)
 N78°E 123.45 P.K. NAIL AND W.C.R.C. TAG IN POWER POLE
 S53°E 52.85 P.K. NAIL AND W.C.R.C. TAG IN MBT POLE
 S20°W 148.62 NAIL AND W.C.R.C. TAG IN MBT POLE
 S35°W 75.93 NAIL AND W.C.R.C. TAG IN MBT POLE (7)
 S57°W 33.78 C/L MBT MANHOLE (8)
 S57°W 32.85 "X" IN N. SIDE MBT MANHOLE (8)
 S85°W 106.99 NAIL AND W.C.R.C. TAG IN MBT POLE
 N47°W 51.72 NAIL AND W.C.R.C. TAG IN POWER POLE

\$ 16.00 MISCELLANEOUS RECORDING
 28 DEC 94 8:16 A.M. RECEIPT# 4A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
 Surveyor's Michigan License No. 24618

Date 12-21-94

2 R
14 E
MIS

1804008750

L127800PA032

ACT 74 SURVEY L19490 PA483
FND 2" IRON PIPE BY RICHARD POSTIFF
IN 1975 (14)
N.W. 38.88 WCRC TAG IN DE POLE (12)
S.W. 106.91 NAIL IN MBT POLE (15)
S.E. 43.68 P.K. NAIL IN MBT POLE (16)

BOARD OF WAYNE CO. RD. COMM
1/2" IRON FOUND IN 1988 (17)
N.E. 92.65 CL HYDRANT (18)
S.E. 43.59 BRASS TAG IN MBT POLE (13)
S.W. 76.32 BRASS TAG IN MBT POLE (7)
S.W. 32.52 "X" ON RIM MBT M.H. (8)
N.W. (NO GIVEN DISTANCE) BRASS TAG IN MBT POLE (12)

MC 1212