

FEB 28 2000

Liber-30836 Page-44
99590871 12/23/1999
F.E. Youngblood, Wayne Co. Register of Deeds
RDANDSYL

SECTION

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)		Located In: <u>NORTHVILLE</u> Corner Code #		
		<u>TOWNSHIP</u>		
1. Public Land Survey	T <u>1 S</u>	R <u>8 E</u>	<u>G-1</u>	
	T _____	R _____	_____	
	T _____	R _____	_____	
	T _____	R _____	_____	
2. Property controlling in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
4. Lot No. _____, Recorded Plat _____				
5. Private Claims _____				

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-7-99

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, CHRISTOPHER S. LAMUS, in a field survey on MARCH 2, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:
DRIG. GOVERNMENT NOTES 1817
WITNESSED BY FLETCHER - SET POST
NO WITNESSES SET

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. ROAD COMMISSION (1964)
MONUMENT (NO DESCRIPTION)
N.W. 87.60' E.D. POLE (1) GONE
S.W. 47.58' 29° ELM (2) GONE
S.LY 33.00' MON. (3) GONE
S.LY 57.68' 14° WALNUT (4) GONE
S.E. 91.28' 32° ELM (5) GONE

WAYNE CO. ROAD COMMISSION (1970)
MONUMENT (NO DESCRIPTION)
N.W. 74.21' *X* IN CONC. MARKER (6) GONE
S.W. 40.35' D.E. POLE (7) GONE
S.LY 91.24' D.E. POLE (8) GONE
S.E. 91.98' D.E. POLE (9) GONE

DISTANCE TO F-1 2621.26' (M) RECORDED AS 2621.66' BY WAYNE COUNTY BUREAU OF TAXATION.
DISTANCE TO H-1 2486.87' (M) RECORDED AS 2485.85' BY WAYNE COUNTY BUREAU OF TAXATION.
DISTANCE TO G-2 2402.88' (M) RECORDED AS 2403.59' BY WAYNE COUNTY BUREAU OF TAXATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 (COMMON CORNER BASED ON G.L.O. NOTES)
5/8" IRON ROD IN SMASHED MON. BOX. MON. BOX WAS REMOVED AND REPLACED.
SET BRASS W.C. WASHER AND SURVEYOR'S CAP #41914 OVER 5/8" IRON ROD IN NEW MON BOX.
CORNER IS LOCATED IN PAVEMENT OF EIGHT MILE ROAD AND TAFT ROAD.
N 37° E 75.56' SET W.C. RE-MON BRASS WASHER IN S.E. SIDE POWER POLE. (10)
S 8° W 73.68' SET W.C. RE-MON BRASS WASHER IN W. SIDE POWER POLE. (11)
S 46° W 57.89' SET W.C. RE-MON BRASS WASHER IN N.W. SIDE POWER POLE. (12)
N 37° W 70.08' SET W.C. RE-MON BRASS WASHER IN E. SIDE POWER POLE. (13)

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/23/99



R LCE 94R 1P 203

