

SURVEY & RECONUMENTATION

FEB 28 1994

COMMISSION

RC 1212

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

27003 PA 590

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>8 E</u>	<u>G 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

93 DEC -3 AM 8:54
FOREST COUNTY REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:

1973 LIBER 18571, PG 154
MONUMENT IN BOX
NE 62.40' SPIKE IN SE SIDE DE POLE (MEAS 62.64')
SLY 33.06' IRON (NOT RECOVERED)
WNW 90.09' R.R. SPIKE S SIDE 16" MAPLE (MEAS 90.82)
NW 33.79 P.K IN SW SIDE 14" OAK (MEAS 33.40')

NOTE: ONE BUREAU OF TAXATION (1930) WITNESSES REMAIN
NW 33.72' 4" OAK (MEAS 24" OAK 33.40')

1979 LIBER 20407, PG 482
IRON IN MON BOX
N 29° W 33.96' PK NAIL SW SIDE 20" OAK (MEAS 33.40')
N 20° E 62.59' PK NAIL NW FACE DE POLE (MEAS 62.64')
S 05° W 32.48' NAIL W FACE MBT POLE (GONE)
N 66° W 90.10' R.R. SPIKE W FACE 18" MAPLE (MEAS 90.82')

WAYNE CO. RD. COMM 1970
FOUND CONC. MONUMENT IN MON. BOX
NW 33.78' 17" OAK (MEAS 33.40')
NE 62.61' D.E. POLE (MEAS 62.64')
SLY 33.01' FD. IRON (NOT RECOVERED)
SW 72.18' STUMP (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONC. MONUMENT IN MONUMENT BOX NEAR CENTERLINE OF FIVE MILE ROAD
S 05° W 52.44' SET NAIL & TAG E. FACE POWER POLE
N 75° W 90.82' SET NAIL & TAG SW FACE 24" MAPLE (PREVIOUS WITNESS)
N 30° W 33.40' SET NAIL & TAG E. FACE 24" OAK (PREVIOUS WITNESS)
N 25° E 62.64' SET NAIL & TAG E. FACE POWER POLE (PREVIOUS WITNESS)

DISTANCE TO H 7 MEASURED AS 2643.33' RECORDED IN 1930 AS 2642.12"
SET REMONUMENTATION DISC AND CAP ON MONUMENT

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer Date NOVEMBER 8, 1993

Surveyor's Michigan License No. 24618

2R
11/8