

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located In: PLYMOUTH TWP. Corner Code #

- 1. Public Land Survey T 1 S R 8 E G-10
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plot _____
- 5. Private Claims _____

Compliance with ACT 345, P.A. 1990 *DOJ*

APPROVED ON: 12-13-1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

96327771

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 5, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1815
 BY JOSEPH WAMPLER - SET POST
 11' BEECH N.45°W. 34 LINKS (1)
 11' BEECH S.17°E. 11LINKS (2)

\$ 4.00 REMONUMENTATION
 \$ 7.00 DEED
 27 DEC 96 11:49 A.M. RECEI A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER EDS
 WAYNE COUNTY, MI

NO G.L.D. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. BUREAU OF TAXATION (1930'S) PUBLIC ACT 74 L.C.R.C. L.18204, P.376
 CONCRETE FENCE POST CONCRETE FENCE POST
 S.E. 76.30' 7' CHERRY (3) GONE IN 9/19/72 BY ROBERT A. CAMPBELL, JR.
 S.E. 28.85' 7' CHERRY (4) GONE WEST 10.00' REFERENCE MON. (9) FOUND
 S.E. 76.50' 5' ELM (5) GONE NORTH 11.40' 4' ELM SPIKE W. SIDE (10) GONE
 EAST 5.78' 4' ELM SPIKE N. SIDE (11) FOUND
 S.W. 19.68' 4' ELM (12) GONE

BOARD OF WAYNE CO. RD. COMM
 CONCRETE FENCE POST (1970'S)
 N.E. 92.90' 15' POPULAR (6) GONE
 S.W. 69.98' 12' ELM (7) GONE
 S.W. 47.41' 9' APPLE (8) GONE FOUND 6'x6'x6' CONC. FENCE POST AS DESCRIBED.

DISTANCE TO G-11 2653.52' (M) RECORDED AS 2654.44' BY WAYNE COUNTY BUREAU OF TAXATION.
 DISTANCE TO REF. MON. WEST 10.00' (R&M) AS RECORDED IN BEACON ESTATES SUBDIVISION. L.88, P.90-91.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10
 6'x6'x6' CONC. FENCE POST AS DESCRIBED.
 UNABLE TO SET W.C. REMON CAP OR SURVEYOR'S CAP DUE TO NATURE OF MONUMENT.
 MONUMENT IS NOT LOCATED IN ANY ROAD RIGHT-OF-WAY.

WEST 10.00' REFERENCE MON. (9) FOUND
 EAST 5.78' 4' ELM SPIKE N. SIDE (11) FOUND
 S.24°E. 55.15' TOP OF FIRE HYDRANT
 S.19°W. 38.97' SET W.C. REMON TAG EAST FACE OF U. POLE
 N.55°W. 23.58' SET W.C. REMON TAG NORTH SIDE OF 10" PINE
 N.70°E. 44.79' SET W.C. REMON TAG SOUTH SIDE OF 10" PINE



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
 Surveyor's Michigan License No. 41914

Date 12/26/96

4R
 7D
 DOJ