

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located In: CITY OF PLYMOUTH Corner Code #

- 1. Public Land Survey T 1 S R 8 E H-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-13-1996

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

96327168

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 2, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:
 ORIG. GOVERNMENT NOTES 1815
 BY JOSEPH WAMPLER - SET POST
 12" SUGAR S.45°E. 30 LINKS (1)
 10" ELM N.23°W. 14 LINKS (2)

\$ 4.00 REMONUMENTATION
 \$ 7.00 DEED
 27 DEC 96 11:49 A.M. RECEI A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER ED3
 WAYNE COUNTY, MI

NO G.L.O. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
 WAYNE CO. BUREAU OF TAXATION (1930'S) PUBLIC ACT 74 L.C.R.C. L18334, P.613
 MONUMENT BOX FOUND BROKEN MONUMENT IN MON. BOX
 ON 1/24/73 BY ROBERT A. CAMPBELL, JR. #13028
 N.E. 45.81' 8" ELM (3) GONE
 EAST 33.07' MONUMENT (4) FOUND
 S.E. 51.84' 8" ELM (5) GONE
 S.W. 54.03' TEL. POLE (6) GONE
 S.W. 32.92' MONUMENT (7) GONE
 WEST 30.28' FOUND PIPE (8) GONE
 N.W. 32.53' 12" ELM (9) GONE
 N.W. 69.97' TEL. POLE (10) GONE
 N.E. 60.69' D.E. POLE (11) FOUND
 EAST 33.14' MONUMENT (4) FOUND
 S.W. 61.67' GUY POLE (13) FOUND

DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS.
 DISTANCE TO H-10 2642.88' (M) 2642.79' (R)
 DISTANCE TO I-10 2752.39' (M) 2752.60' (R)
 FOUND 1/2" BAR IN BROKEN MON. IN BROKEN MON. BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-9
 1/2" BAR IN BROKEN MON. IN BROKEN MON. BOX (MONUMENT BOX SHOULD BE REPLACED)
 UNABLE TO SET W.C. REMON CAP AND SURVEYOR'S CAP DUE TO CONDITION OF MONUMENT.
 N.41°E. 60.73' SET W.C. REMON TAG IN D.E. POLE (11) FOUND
 EAST 33.70' MONUMENT, MON. WAS FOUND LEANING TO THE EAST (4) FOUND
 S.64°W. 61.35' SET W.C. REMON TAG IN GUY POLE (13) FOUND
 S.08°E. 102.00' SET W.C. REMON TAG IN E. FACE OF POWER POLE



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
 Surveyor's Michigan License No. 41914

Date 12/26/96

4R
70
D.P.J.