

L129363PA295

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In: CITY OF PLYMOUTH Corner Code #

- 1. Public Land Survey T 1 S R 8 E I-12
2. Property controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plot
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-13-1996
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 2, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

Grid table with columns A-KL and rows 2-13. A dot is marked at the intersection of column J and row 12.

A. Description of original monument and accessories and/or subsequent restoration:
ORIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
6" BEECH N.54°E. 6 LINKS (1)
7" BEECH S.63°W. 13 LINKS (2)

4.00 REMONUMENTATION
\$ 7.00 DEED
27 DEC 96 11:49 A.M. RECEI A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER EDS
WAYNE COUNTY, MI

NO G.L.D. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:
WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT
N.E. 59.33' EDISON POLE (3) GONE
S.E. 72.57' CROSS CUT IN CURB (4) GONE
S.E. 86.67' CURB @ GAS STAT. (5) GONE
S.W. 60.27' TEL. POLE (6) GONE
N.W. 60.41' FIRE HYDRANT (7) GONE
PUBLIC ACT 74 L.C.R.C. L.18806. P.440
FOUND 1' IRON PIPE IN MON. BOX
N.40°E 47.70' M.B.T. MANHOLE (11) GONE
S.40°E 47.08' M.B.T. MANHOLE (12) GONE
S.60°W. 75.23' WATER GATE VALVE M.H. (13) GONE
N.30°W. 60.60' TOP OF FIRE HYDRANT (7) GONE

BOARD OF WAYNE CO. RD. COMM MONUMENT IN MON. BOX (3/1970 BY R. ABAR)
N.E. 89.59' D.E. POLE (8) GONE
S.E. 59.08' M.B.T. POLE (9) GONE
S.W. 74.09' GUY POLE (10) FOUND
S.W. 60.27' TEL. POLE (6) GONE
PUBLIC ACT 74 L.C.R.C. L.21005. P.849
FOUND 1' IRON PIPE IN MON. BOX
S.40°W 62.6 FIRE HYDRANT (14) GONE
S.40°E 64.2' NAIL IN POLE (15) GONE
FOUND 1' IRON PIPE SET IN CONCRETE IN MON. BOX

DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS.
DISTANCE TO I-11 2647.59' (M) 2647.81' (R)
DISTANCE TO J-12 2656.04' (M) 2656.04' (R) ALSO AS 2656.25' (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12
1' IRON PIPE SET IN CONCRETE IN MON. BOX.
MON. BOX IS LOCATED IN MAIN ST. RIGHT-OF-WAY IN ASPHALT PAVEMENT
SET W.C. REMON CAP AND SURVEYOR'S CAP # 41914 ON TOP OF IRON PIPE.

N.60°W. 81.52' SET W.C. REMON TAG S.W. SIDE OF D.E. POLE
N.60°E. 90.91' SET W.C. REMON TAG S.E. SIDE OF D.E. POLE
S.52°W. 74.09' CENTER OF GUY POLE (10) FOUND
S.30°E. 62.77' CENTER OF 'X'-WALK SIGNAL POLE



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/26/96

Handwritten initials: 4R, 7D, DPJ