

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located In: CITY OF PLYMOUTH Corner Code #

- 1. Public Land Survey T 1 S R 8 E J-9
2. Property controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plot
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-13-1996
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

96327765

Grid table with columns A-KL and rows 2-13. A dot is marked at the intersection of column J and row 9.

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:
DRIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
9° CHERRY N.03°W. 32 LINKS (1)
WHITE OAK S.31°E. 26 LINKS (2)

\$ 4.00 REMONUMENTATION
\$ 7.00 DEED
27 DEC 96 11:49 A.M. RECEI A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER EDS
WAYNE COUNTY, MI

NO G.L.D. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. BUREAU OF TAXATION (1930'S) BOARD OF WAYNE CO. RD. COMM
PIPE IN SQUARE IRON BOX BETWEEN PIPE IN SQUARE IRON BOX BETWEEN
R.R. TRACKS R.R. TRACKS
N.E. 44.58' SIGNAL BOX (3) GONE N.E. 44.58' SIGNAL BOX (3) GONE
N.W. 41.50' SIGNAL BOX (4) GONE N.W. 41.50' SIGNAL BOX (4) GONE
WAYNE CO. BUREAU OF TAXATION PUBLIC ACT 74 L.C.R.C. L.18045, P.937
PIPE IN SQUARE IRON BOX BETWEEN 3/4" IRON PIPE IN SQUARE MON. BOX IN CENTERLINE OF N. MILL ST.
R.R. TRACKS IN 4/14/72 BY ROBERT A. CAMPBELL, JR. #13028
N.E. 44.58' SIGNAL BOX (3) GONE S.W. 45.22' MONUMENT (6) GONE
N.W. 41.50' SIGNAL BOX (4) GONE N.W. 41.30' MONUMENT (7) FOUND
NORTH 4.50' CENTERLINE OF WEST BOUND TRACK N.E. 41.09' MONUMENT (8) FOUND
(5) FOUND NORTH 2.48' SOUTH RAIL OF W. BOUND MAIN (9) FOUND
FOUND 3/4" IRON PIPE IN SQUARE MON. BOX. BOX LID HAS "M" ON TOP.

DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS.
DISTANCE TO I-9 2646.92' (M) 2647.12' (R)
DISTANCE TO J-10 2670.27' (M) 2671.20' (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9
3/4" IRON PIPE IN SQUARE MON. BOX. BOX LID HAS "M" ON TOP.
SET W.C. REMON CAP AND SURVEYOR'S CAP # 41914 ON IRON PIPE.
MONUMENT BOX IS 6" BELOW ASPHALT SURFACE IN MAIN ST. RIGHT-OF-WAY.
N.45°W. 41.30' MONUMENT (7) FOUND
N.45°E. 41.09' MONUMENT (8) FOUND
NORTH 2.48' SOUTH RAIL OF W. BOUND MAIN (9) FOUND
NORTH 4.50' CENTERLINE OF WEST BOUND TRACK (5) FOUND
S.45°W. 35.27' SET W.C. REMON TAG N.W. SIDE OF P. POLE.
S.45°E. 37.31' CENTERLINE OF RAILROAD SIGNAL POST.

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/26/96



Handwritten initials and numbers: 4R, 70, and a signature.