

U29363M294

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE
(County)

Located in: CITY OF PLYMOUTH Corner Code #

- 1. Public Land Survey T 1 S R 8 E J-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plot _____
- 5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-13-1996

WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

96327766

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 5, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
13' W. DAK S.23°W. 38 LINKS (1)
11' W. DAK N.45°E. 3 LINKS (2)

\$ 4.00 REMONUMENTATION
\$ 7.00 DEED
27 DEC 96 11:49 A.M. RECEI A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER EDS
WAYNE COUNTY, MI

NO G.L.D. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT EASTERLY 24.50' GUY POLE (3) GONE S.E. 46.70' POLE (4) GONE S.W. 29.48' 16' MAPLE (5) GONE WESTERLY 19.05' 'X' IN SIDEWALK (6) GONE N.W. 70.22' ED. POLE (7) GONE PUBLIC ACT 74 L.C.R.C. L.19014, P.193 FND IRON PIPE IN MON. BOX IN 11/27/74 BY R.W. SWANSON N.W. 57.51' M.B.T. POLE (8) FOUND EASTERLY 27.80' M.B.T. POLE (9) FOUND S.W. 38.28' DE. POLE (10) FOUND DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS. DISTANCE TO K-11 2655.40' (M) 2655.62' (R) DISTANCE TO J-12 2654.95' (M) 2654.71' (R)	PUBLIC ACT 132 SURVEY L.21910, P.203-204 FND IRON PIPE IN MON. BOX IN 8/06/83 BY RALPH J. LANDINI #16933 WEST 57.54' M.B.T. POLE (8) FOUND S.82°E. 27.63' M.B.T. POLE (9) FOUND S.37°W. 38.29' DE. POLE (10) FOUND N.43°W. 50.50' STREET SIGN (11) FOUND FOUND P.K. INSIDE 3/4" PIPE IN MONUMENT BOX
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11
P.K. INSIDE 3/4" PIPE IN MONUMENT BOX
SET W.C. REMON CAP AND SURVEYOR'S CAP # 41914 ON IRON PIPE.
MON. BOX IS LOCATED IN LILLEY RD. RIGHT-OF-WAY IN ASPHALT PAVEMENT.

N.80°W 57.64' SET W.C. REMON TAG N. FACE OF POWER POLE
S.82°E. 27.58' M.B.T. POLE (9) FOUND
S.37°W. 38.26' DE. POLE (10) FOUND
N.26°E. 112.27' SET W.C. REMON TAG S.W. FACE POWER POLE
N.12°W. 89.54' SET W.C. REMON TAG E. FACE POWER POLE



HR
TD
DPJ

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/26/96