

\$ 4.00 REMONUMENTATION
\$ 10.00 DEED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
RECORDED
DEC 95 3:24 P.M.
FOREST E. YOUNGBLOOD, REGISTER
WAYNE COUNTY, MI

LIBER 28482 PAGE 690

For corners in

WAYNE
(County)

Located in:
PLYMOUTH TWP

Corner Code #

- 1. Public Land Survey T 1 S R 8 E J-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-13-95
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

COMMISSION

REVISITED ON 12-12-95

I, PAUL V. SCHWIMMER, in a field survey on JANUARY 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L
2											
3											
4											
5											
6											
7											
8											
9											
10											
11											
12											
13											

A. Description of original monument and accessories and/or subsequent restoration:

- ORIG. GOVERNMENT NOTES 1815, WITNESSED BY BALESS JIMMINGS - SET POST (1)
- SUGAR MAPLE 16' S 12' W 34 LINKS (2)
- LYNN 15' N 09' W 37 LINKS (3)
- WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (NO DESCRIPTION) (4)
- N.E. 91.62' NAIL IN 10" MAPLE (5)
- N.E. 43.48' NAIL IN 10" ELDER (6)
- S.W. 33.20' NAIL IN TELE POLE (7)
- S.W. 86.90' NAIL IN TELE POLE (8)
- WLY. 221.14' MONUMENT (NO DESCRIPTION) (9)
- BOARD OF WAYNE CO. RD. COMM MONUMENT IN BOX (NO DESCRIPTION) FOUND IN 1970 (4)
- N.E. 91.83' 24' MAPLE (5)
- N.E. 60.10' 30' MAPLE (10)
- WLY. 221.18' MONUMENT (NO DESCRIPTION) (9)
- N.W. 63.26' BELL POLE (11)

CONTINUED ON BACK

95274744

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

J-13 IS NOT A CLOSING CORNER TO THE ADJACENT TOWNSHIP
THE FOLLOWING WITNESSES TO THE CORNER WERE RECOVERED:

- FOUND 3/4" IRON PIPE IN MONUMENT BOX AT INTERSECTION JOY ROAD AND LILLEY ROAD (15)
- N 20° E 90.84' P.K. NAIL IN S. SIDE 36" MAPLE (5)
- WEST 221.00' FOUND P&C IN MONUMENT BOX RLS# 12578 (9)



WAYNE COUNTY REMONUMENTATION
TAGS WERE PUT ON ALL APPROPRIATE
WITNESSES AND REMONUMENTATION
DISKS WERE PLACED ON THE
PHYSICAL MONUMENT

C. Description of monuments for corner and accessories established to perpetuate locating the position of the corner:

- J-13
- FOUND 3/4" IRON PIPE IN MONUMENT BOX AT INTERSECTION JOY ROAD AND LILLEY ROAD (15)
- N 20° E 90.84' P.K. NAIL IN S. SIDE 36" MAPLE (5)
- N 50° E 50.99' 60d NAIL IN SW SIDE GUY POLE FOR TRAFFIC LIGHTS (20)
- N 50° E 51.42' P.K. NAIL IN S.E. SIDE GUY POLE FOR TRAFFIC LIGHTS (21)
- N 51° E 95.47' S.W. BASEMENT CORNER (16)
- S 42° W 69.31' NAIL W/ W.C.R.C. TAG IN S.E. SIDE GUY POLE FOR TRAFFIC LIGHTS (17)
- S 42° W 69.25' P.K. NAIL IN N.W. SIDE GUY POLE FOR TRAFFIC LIGHTS (18)
- WEST 221.00' FOUND P&C IN MONUMENT BOX RLS# 12578 (9)
- DIST TO S.W. CORNER SECTION 35 2647.05' MEAS & 2647.71 REC IN 1930'S
- DIST TO S.E. CORNER SECTION 35 2650.62' MEAS & 2650.61 REC IN 1930'S

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer

Date 12-13-95

Surveyor's Michigan License No. 24618

42
10 D

ACT 132 SURVEY CS1371
FOUND MONUMENT IN BOX
BY BRENDER-HAMILL AND ASSOCIATES IN 1977 (4)
S.E. 51.81' NAIL IN MBT POLE (12)
S.W. 73.51' NAIL IN 24' TREE (13)
N.W. 48.75' NAIL IN GUY POLE (14)

ACT 74 SURVEY L22464 PA198
FND 3/4' IRON ROD IN MONUMENT BOX
BY WALTER ZBIKOWSKI IN 1985 (15)
N 62° E 95.5' S.W. CORNER OF BASEMENT OF HOUSE (16)
S 60° E 48.00' P.K. IN N. SIDE SIGNAL POLE (17)
S 08° W 42.4' CENTER POST OF 3-POST TRAFFIC SIGN (18)
N 61° W 51.1' P.K. IN SOUTH SIDE OF SIGNAL POLE (19)