

SURVEY & RECONSTRUCTION

RC 1213

27003 PA 591

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in

WAYNE (County) Located In: Corner Code #
1. Public Land Survey T 1 S R 8 E K 3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

93 DEC -3 AM 8:54
FOREST COUNTY REGISTER OF DEEDS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A black dot is present in the cell corresponding to row 3, column J.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: PREVIOUSLY RECORDED IN:

WAYNE CO. RD. COMM 1970
FOUND CONC. MONUMENT IN MON. BOX (NO COVER)
NW 32.69' 12" MAPLE (GONE)
NE 39.54' D.E. POLE (MEAS 39.48')
SE 78.53' MBT POLE (GONE)
SW 49.14' MBT POLE (GONE)

NOTE: NO BUREAU OF TAXATION 1930 WITNESSES REMAIN (1930)

1989 LIBER 24088, PG 804
FOUND IRON IN MONUMENT BOX
N 40° E 39.53' NAIL E SIDE UTIL POLE (MEAS 39.48')
S 70° E 80.28' NAIL NE SIDE UTIL POLE (GONE)
S 50° E 49.11' NAIL N SIDE UTIL POLE (GONE)
N 34° E 91.50' SE CORNER BRICK HSE #41400 (MEAS 91.42')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONC. MONUMENT IN MONUMENT BOX NEAR CENTERLINE OF SEVEN MILE ROAD
N 05° E 47.81' SET NAIL & TAG WLY FACE 5" MAPLE
N 35° E 39.48' SET NAIL & TAG ELY FACE P. POLE (PREVIOUS WITNESS)
N 25° E 91.42' SE CORNER BRICK HSE #41400 (PREVIOUS WITNESS)
SLY 20.04' SET NAIL & TAG 0.1' NORTH OF SLY EDGE OF PYMT
S 30° E 128.88' SET NAIL & TAG NE FACE 12" OAK
NLY 60.12' FOUND 'T' IRON
DISTANCE TO L 3 MEASURED AS 2641.33' RECORDED IN 1930 AS 2641.43'
DISTANCE TO J 3 MEASURED AS 2641.03' RECORDED IN 1930 AS 2640.73'
SET REMONUMENTATION DISC AND CAP ON MONUMENT



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer Date NOVEMBER 8, 1993

Surveyor's Michigan License No. 24618

Handwritten initials '2R' and '11/8'