

L129363PA292

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)

Located In: CITY OF PLYMOUTH Corner Code #

- 1. Public Land Survey T 1 S R 8 E K-10
2. Property controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plot
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-13-1996
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Grid table with columns A-K and rows 1-13. A dot is present at row 10, column K.

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
4' B. OAK S.71°W. 7 LINKS (1)
5' B. OAK N.71°E. 15 LINKS (2)

\$ 4.00 REMONUMENTATION

\$ 7.00 DEED

27 DEC 96 11:48 A.M. RECEIVED
RECORDED
FOREST E. YOUNGBLOOD, REGISTER EDG
WAYNE COUNTY, MI

NO G.L.D. WITNESSES REMAIN

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT
N.E. 174.77' 14' SPRUCE (3) GONE
EAST 11.81' 18' SPRUCE (4) GONE
S.W. 38.66' 14' SYCAMORE (5) GONE
PUBLIC ACT 74 L.C.R.C. L.18045, P.935
IRON CLAD CONCRETE MONUMENT FLUSH WITH LAWN
IN 4/14/72 BY ROBERT A. CAMPBELL, JR. #13028
S'LY 44.68' SPIKE EAST SIDE LARGE SPRUCE (6) FOUND
SW'LY 44.42' SPIKE N.W. SIDE LARGE SPRUCE (7) FOUND
SW'LY 59.67' 'STARKWEATHER' PLOT GRAVEMARKER (8) FOUND
NW'LY 100.95' SOUTHEAST CORNER BLOCK BUILDING (9) FOUND
FOUND 1' IRON PIPE, SURROUNDED BY CONCRETE, ENCASED IN

DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS.

DISTANCE TO L-10 2640.32' (M) 2641.06' (R)
DISTANCE TO K-11 2622.44' (M) 2622.65' (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10
1' IRON PIPE, SURROUNDED BY CONCRETE, ENCASED IN
3' IRON PIPE, FLUSH WITH GROUND AND IT IS NOT IN ANY ROAD RIGHT-OF-WAY.
SET SURVEYOR'S CAP # 41914 IN IRON PIPE, UNABLE TO SET W.C. REMON CAP DUE TO SIZE OF PIPE
S.12°W. 44.63' SET W.C. REMON TAG EAST SIDE 28' SPRUCE (6) FOUND
S.50°W. 44.26' SET W.C. REMON TAG N.W. SIDE 29' SPRUCE (7) FOUND
S.58°W. 59.69' N.W. CORNER OF 'STARKWEATHER' PLOT GRAVEMARKER (8) FOUND
N69°W. 101.10' SOUTHEAST CORNER BLOCK BUILDING (9) FOUND



THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/26/96