

SURVEY & RECONSTRUCTION

RC 1215

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LI27003 PA 593

REGISTERED LAND SURVEYOR  
PAUL V. SCHWIMMER  
MICHIGAN STATE BOARD OF LAND SURVEYORS

For corners in

WAYNE  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 1 S R 8 E K 11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, PAUL V. SCHWIMMER, in a field survey on OCTOBER 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.D. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: PREVIOUSLY RECORDED IN:

1972 LIBER 17980, PG 928  
IRON 0.6' BELOW SURFACE IN C/L OF WEST BOUND  
LANE OF ANN ARBOR TRAIL  
NE 39.98' SPIKE IN W SIDE 12' CEDAR (MEAS 40.24')  
SE 38.88' SPIKE IN W SIDE 8' MAPLE (MEAS 38.90')  
SE 73.80' SPIKE IN NE SIDE MBT POLE (MEAS 73.80')

NOTE: ONE 1930 BUREAU OF TAXATION  
WITNESS REMAINS  
NNE 40.05' 16' CEDAR (MEAS 40.24')

WAYNE COUNTY ROAD COMMISSION WITNESSES 1973  
IRON 4' BELOW SURFACE  
NE 39.99' 17' CEDAR (MEAS 40.24')  
SE 73.68' BELL POLE (MEAS 73.80')  
SE 38.87' 7' OAK (MEAS 38.90')  
S 33.02' MONUMENT (MEAS 33.02')  
SW 91.73' 11' MAPLE (MEAS 91.39')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 3/4" IRON PIPE IN MONUMENT BOX, RAISED WITH 1/2" STEEL ROD WITH DISC  
N 20° E 40.24' SET NAIL & TAG E FACE 18" CEDAR (PREVIOUS WITNESS)  
S 15° E 38.90' SET NAIL & TAG SW FACE 18" MAPLE (PREVIOUS WITNESS)  
S 45° W 69.63' SET NAIL & TAG NW FACE 18" TWIN MAPLE  
S 75° W 91.39' SET NAIL & TAG SE FACE 18" MAPLE (PREVIOUS WITNESS)  
N 40° W 57.97' SET NAIL & TAG NE FACE 14" MAPLE  
S 65° E 73.80' FOUND NAIL NE SIDE MBT POLE (PREVIOUS WITNESS)  
SLY 33.02' FOUND CONCRETE MONUMENT (PREVIOUS WITNESS)

DISTANCE TO WLY 1/8TH CORNER MEASURED AS 1321.11' RECORDED IN 1930 AS 1320.95'  
DISTANCE TO L 11 MEASURED AS 2610.07' RECORDED IN 1930 AS 2652.59' ← CAUTION!  
SET REMONUMENTATION DISC AND CAP ON IRON

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by Paul V. Schwimmer

Date NOVEMBER 16, 1993

Surveyor's Michigan License No. 24618

2R  
11K D