

\$ 4.00 REMONUMENTATION

\$ 10.00 DEED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
RECEIPT# 76A
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

WAYNE
(County)

Located In:
PLYMOUTH TWP

Corner Code #

- 1. Public Land Survey T 1 S R 8 E K-13
- 2. Property controlling in Section S T R SURVEY & REMONUMENTATION
- 3. Miscellaneous Property in Sec. S T R APR 05 1996
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

COMMISSION

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-13-95
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

95274748

REVISITED 12-12-95
JANUARY 30, 19 95

I, PAUL V. SCHWIMMER, in a field survey on JANUARY 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	A
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

- ORIG. GOVERNMENT NOTES 1815, WITNESSED BY BALESS JIMMINGS - SET POST (1)
- WHITE OAK S 59° E 12 LINKS (2)
- BLACK OAK N 82° W 14 LINKS (3)
- WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (NO DESCRIPTION) (4)
- N.E. 66.90' CROSS IN CONC. STEP (5)
- N.E. 47.25' 4" LOCUST (6)
- ELY. 67.25' 6" LOCUST (7)
- WLY. 317.23' MONUMENT (NO DESCRIPTION) (8)
- N.W. 29.3' 30" MAPLE (9)
- BOARD OF WAYNE CO. RD. COMM MONUMENT IN BOX FOUND IN 1970 (4)
- N.W. 52.12' NAIL IN DE POLE (10)
- N.E. 67.14' "X" ON CONC. STEP (5)
- SLY. 33.06' MONUMENT (NO DESCRIPTION) (11)
- S.W. 61.73' NAIL IN BELL POLE (12)
- N.W. 56.97' NAIL IN WOOD POST (13)



CONTINUED ON BACK

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

- K-13 IS NOT A CLOSING CORNER WITH THE ADJACENT TOWNSHIP
- THE FOLLOWING WITNESSES TO THE CORNER WERE FOUND:
- FOUND 1" IRON PIPE IN MONUMENT BOX (14)
- N 03° W 52.14' P.K. NAIL IN W. SIDE POWER POLE (10)
- N 03° W 51.70' P.K. NAIL IN S. SIDE POWER POLE (10)
- N 03° W 52.11' 16d NAIL IN E. SIDE POWER POLE (10)
- N 03° W 52.13' 16d NAIL IN E. SIDE POWER POLE (10)
- N 03° W 52.12' NAIL AND W.C.R.C. TAG IN E. SIDE OF POWER POLE "REFERENCE POINT W.C.R.C." (10)
- N 67° E 133.46' P.K. NAIL IN S. SIDE POWER POLE (15)
- N 67° E 133.27' 16d NAIL IN S. SIDE POWER POLE (15)
- S 70° E 143.63' CENTER LINE TOP NUT ON FIRE HYDRANT (16)
- SOUTH 33.06' STEEL ENCASED CONCRETE MONUMENT (BURIED 2') (11)
- N 89° W 317.35' 1/2" RE-BAR IN MONUMENT BOX (8)

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13
- FOUND 1" IRON PIPE IN MONUMENT BOX (14)
- N 03° W 52.14' P.K. NAIL IN W. SIDE POWER POLE (10)
- N 03° W 51.70' P.K. NAIL IN S. SIDE POWER POLE (10)
- N 03° W 52.11' 16d NAIL IN E. SIDE POWER POLE (10)
- N 03° W 52.13' 16d NAIL IN E. SIDE POWER POLE (10)
- N 03° W 52.12' NAIL AND W.C.R.C. TAG IN E. SIDE OF POWER POLE "REFERENCE POINT W.C.R.C." (10)
- N 67° E 133.46' P.K. NAIL IN S. SIDE POWER POLE (15)
- N 67° E 133.27' 16d NAIL IN S. SIDE POWER POLE (15)
- S 70° E 143.63' CENTER LINE TOP NUT ON FIRE HYDRANT (16)
- SOUTH 33.06' STEEL ENCASED CONCRETE MONUMENT (BURIED 2') (11)
- N 89° W 317.35' 1/2" RE-BAR IN MONUMENT BOX (8)
- 1ST TO CENTER SECTION 35 2638.58' MEAS & 2638.46' REC IN 1930'S
- 1ST TO S 1/4 SECTION 35 2650.62' MEAS & 2650.61' REC IN 1930'S
- 1ST TO S 1/4 SECTION 36 2640.19' MEAS & 2640.24' REC IN 1930'S

WAYNE COUNTY REMONUMENTATION TAGS WERE PUT ON ALL APPROPRIATE WITNESSES AND REMONUMENTATION DISKS WERE PLACED ON THE PHYSICAL MONUMENT

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
Surveyor's Michigan License No. 24618

Date 12-11-95

42

ACT 74 SURVEY L18491 PA347
FND IRON BY ROBERT C. WADE RLS #11868
IN 1973 (14)
N 02°18' W 52.04' DOUBLE HEADED NAIL IN POWER POLE (10)
N 67°03' E 133.27' NIAL IN S. SIDE POWER POLE (15)
S 70°35' E 143.62' CENTER TOP OF FIRE HYDRANT (16)

LIBER 28482 PAGE 699

ACT 74 SURVEY L18605 PA075
FND IRON IN MONUMENT BOX BY RAPHAEL J. LANDINI RLS# 16933
IN 1973 (14)
NORTH 52.10' P.K. IN UTILITY POLE (10)
S 60° E 143.72' TOP BOLT IN HYDRANT (16)
S 05° W 33.00' MONUMENT (NO DESCRIPTION) (11)
S 70° W 61.69' NAIL IN UTILITY POLE (12)

ACT 74 SURVEY L21876 PA871
FND 1" IRON PIPE IN CONCRETE MONUMENT
BY ROBERT PITTS RLS# 10702 IN 1983 (14)
S.E. 143.58' CUT "X" ON S.E. FACE OF FIRE HYDRANT FLANGE (16)
S.W. 50.95' NAIL W/ W.C.R.C. TAG IN S.E. SIDE 16" BOX ELDER CLUMP (17)
WEST 317.23' #4 RE-ROD, N.W. CORNER SEC. 1, T.2S, R.8E. (8)

FILED DO NOT WRITE