

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In: PLYMOUTH TWP. Corner Code #

- 1. Public Land Survey T 1 S R 8 E L-9
2. Property controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plot
5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-13-1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, CHRISTOPHER S. LAMUS, in a field survey on DECEMBER 2, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

DRIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
4' ASH N.11°W. 8 LINKS (1)
6' ASH S.41 1/2°W. 24 LINKS (2)

NO G.L.D. WITNESSES REMAIN

\$ 4.00 REMONUMENTATION

\$ 7.00 DEED

27 DEC 96 11:48 A.M. RECEI A
RECORDED
FOREST E. YOUNGBLOOD, REGISTER EDS
WAYNE COUNTY, MI

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. BUREAU OF TAXATION (1930'S) PUBLIC ACT 74 L.C.R.C. L.17940, P.231
SPIKE (ROSE POINT) FOUND FIVE (5) NAILS IN TIE (ROSE POINT).
ON 12/17/71 BY ROBERT A. CAMPBELL, JR. #13028
NORTH 97.47' R.R. IRON (3) GONE
N.E. 88.13' TEL. POLE (4) FOUND
S.E. 166.00' 12' ELM (5) GONE
S.W. 84.55' D.E. POLE (7) GONE
SOUTH 27.52' CENTERLINE OF WEST BOUND TRACK (6) FOUND
S.W. 84.55' D.E. POLE (7) GONE
BOARD OF WAYNE CO. RD. COMM
SPIKE (ROSE POINT) (1970'S)
NORTH 97.47' R.R. IRON (3) GONE
N.E. 88.13' TEL. POLE (4) FOUND
S.E. 166.00' 12' ELM (5) GONE
S.W. 84.55' D.E. POLE (7) GONE
SOUTH 27.52' CENTERLINE OF WEST BOUND TRACK (6) FOUND
PUBLIC ACT 74 L.C.R.C. L.18829, P.639
LOCATED ROSE POINT BY WITNESSES
ON 5/1/74 BY MYRON I. PETRIE
N.20°E. 87.54' NAIL & M.S.H.D. TAG E.SIDE OF D.E. POLE (8) FOUND
SOUTH 83.79' NAIL IN E. SIDE OF D.E. POLE (9) FOUND
S.43°W 93.13' 1/2" PINCHED PIPE W/ P.K. IN TOP. (10) GONE
S.45°E 100.50' 3/4" PINCHED PIPE W/ P.K. IN TOP. (11) GONE
FOUND FIVE (5) NAILS IN TIE (ROSE POINT)
DISTANCES TO ADJOINING SECTION CORNERS FROM WAYNE COUNTY BUREAU OF TAXATION RECORDS.
DISTANCE TO M-9 2660.37' (M) 2660.83' (R)
DISTANCE TO K-9 2633.72' (M) 2634.26' (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9
FIVE (5) NAILS IN TIE (ROSE POINT)
REPLACED CENTER NAIL WITH W.C. REMON CAP AND P.K. UNABLE TO SET SURVEYOR'S CAP.
SECTION CORNER IS LOCATED IN RAILROAD RIGHT-OF-WAY IN RAILROAD TIE.

N.20°E. 87.65' NAIL & M.S.H.D. TAG E.SIDE OF D.E. POLE (8) FOUND
SOUTH 83.80' SET W.C. REMON TAG IN E. SIDE OF D.E. POLE (9) FOUND
S.20°W. 168.43' SET W.C. REMON TAG N. FACE OF POWER POLE
N.30°W. 117.56' SET W.C. REMON TAG S.W. FACE OF TEL. POLE

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Christopher S. Lamus
Surveyor's Michigan License No. 41914

Date 12/26/96

