

\$ 4.00 REMONUMENTATION

\$ 10.00 DEED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act '74, Mich. P.A. 1970

RECEIVED  
RECORDED  
DEC 95 3:25 P.M.  
FOREST E. YOUNGBLOOD, REGISTER  
WAYNE COUNTY, MI

05274750

For corners in

WAYNE

(County)

Located in:

PLYMOUTH TWP

Corner Code #

L-13

1. Public Land Survey

T 1 S R 8 E

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

APR 05 1996

COMMISSION

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-13-95  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, PAUL V. SCHWIMMER, in a field survey on JANUARY 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:  
 ORIG. GOVERNMENT NOTES 1815, WITNESSED BY BALESS JIMMINGS - SET POST (1)  
 RED OAK 8' N 80° E 9 LINKS (2)  
 IRONWOOD 8' S 40° W 16 LINKS (3)  
 WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (NO DESCRIPTION) (4)  
 N.E. 67.10' E.D. POLE (5)  
 S.E. 62.55' GUY POLE (6)  
 S.E. 43.68' 24" MAPLE (7)  
 WLY. 152.74' MONUMENT (8)  
 N.W. 84.40' BUILDING CORNER (9)

- BOARD OF WAYNE CO. RD. COMM MONUMENT IN BOX (NO DESCRIPTION) FOUND IN 1970 (4)  
 S.E. 61.97' MBT POLE (10)  
 S.E. 43.64' 24" MAPLE (7)  
 S.W. 11.58' "X" ON N. RIM OF M.H. (11)  
 WLY. 152.76' IRON (8)

CONTINUED ON BACK

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

- L-13 FOUND COPPERWELD ROD IN MONUMENT BOX AT CENTER LINE JOY ROAD  
 THE FOLLOWING WITNESSES WERE RECOVERED:  
 N 14° W 88.78' P.K. NAIL IN POWER POLE (12)  
 S 28° E 137.43' N.E. BUILDING CORNER (14)  
 S 15° W 120.44' N.W. BUILDING CORNER (15)  
 N 16° W 88.78' NAIL AND MDT TAG IN E. FACE UTILITY POLE (12)  
 S 88° W 152.73' N 1/4 CORNER SEC 1 T.2.S. R.8.E. COPPERWELD ROD IN MONUMENT BOX (8)

L-13 IS NOT A CLOSING CORNER TO THE ADJACENT TOWNSHIP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 FOUND COPPERWELD ROD IN MONUMENT BOX  
 N 14° W 88.78' P.K. NAIL IN POWER POLE (12)  
 S 28° E 137.43' N.E. BUILDING CORNER (14)  
 S 15° W 120.44' N.W. BUILDING CORNER (15)  
 N 16° W 88.78' NAIL AND MDT TAG IN E. FACE UTILITY POLE (12)  
 S 88° W 152.73' N 1/4 CORNER SEC 1 T.2.S. R.8.E. COPPERWELD ROD IN MONUMENT BOX (8)  
 DIST TO S.W. CORNER SECTION 36 2540.19' MEAS & 2640.24' REC  
 DIST TO S.E. CORNER SECTION 36 2631.84' MEAS & 2634.14' REC

WAYNE COUNTY REMONUMENTATION  
TAGS WERE PUT ON ALL APPROPRIATE  
WITNESSES AND REMONUMENTATION  
DISKS WERE PLACED ON THE  
PHYSICAL MONUMENT

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer

Date 12-13-95

Surveyor's Michigan License No. 24618

ACT 74 SURVEY L18491 PA343

FND IRON BY ROBERT WADE RLS# 11868

IN 1973 (4)

N 14° W 88.83' P.K. NAIL IN POWER POLE (12)

S 34° E 80.15' P.K. NAIL IN 4" X 12" POWER POLE (13)

S 26° E 137.43' BUILDING CORNER (14)

S 17° W 120.24' BUILDING CORNER (15)

N 89°52'07" W (REC) 152.74' N 1/4 CORNER SEC 1 T.2.S. R.8.E. (8)

ACT 74 SURVEY L.21297 PA.923

FND 1" IRON BY ERVIN P. MILLER RLS# 13589

IN 1981 (4) REPLACED WITH COPPERWELD ROD IN MONUMENT BOX (4)

N 42° E 132.81' NAIL AND MDOT TAG IN W. FACE OF UTILITY POLE (16)

S 28° E 137.36' N.E. BUILDING CORNER (14)

S 15° W 120.25' N.W. BUILDING CORNER (15)

N 16° W 88.65' NAIL AND MDOT TAG IN E. FACE UTILITY POLE (12)

S 88° W 152.69' N 1/4 CORNER SEC 1 T.2.S. R.8.E. COPPERWELD ROD IN MONUMENT BOX (8)

FILED DO NOT MAIL