

DEC 29 1998

SURVEY & REMONUMENTATION

MAR 02 1999

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE (County)

Located In: NORTHVILLE TWP. Corner Code #

Table with 4 columns: Item, T, R, M-3. Rows include Public Land Survey, Property controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-8-98
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plot
5. Private Claims

I, CHRISTOPHER S. LAMUS, in a field survey on FEBRUARY 18, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

Grid table with columns A-L and rows 2-13. Contains numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

ORIG. GOVERNMENT NOTES 1815
BY JOSEPH WAMPLER - SET POST
14" SUGAR N.35°W. 2 LINKS (1)
30" POPULAR S.7°E. 13 LINKS (2)

NO G.L.O. WITNESSES REMAIN

\$7.00 DEED
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #101861
\$4.00 REMONUMENTATION

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

WAYNE CO. ROAD COMMISSION 1974
(M-3) FOUND MONUMENT IN MON. BOX
SOUTH 127.58' MON. IN MON.BOX (1)
S.EAST 51.55' TO D.E. POLE (2) GONE
N.EAST 86.07' D.E. POLE (3) GONE
N.WEST 31.91' D.E. POLE (4) GONE
N.WEST 44.57' D.E. POLE (5) GONE

WAYNE CO. ROAD COMMISSION 1976
(M-3) FOUND MONUMENT IN MON. BOX
SOUTH 127.58' MON. IN MON.BOX (1)
S.EAST 51.94' TO D.E. POLE (2) GONE
N.EAST 86.11' D.E. POLE (3) GONE
N.WEST 44.60' D.E. POLE (5) GONE

PUBLIC ACT 74 L.C.R.C. L.27276 P.696
(M-3) FOUND IRON IN MON. BOX
N.63E 55.74' P.K. N.FACE U.POLE (6)
S74°E 49.55' P.K. N.FACE U.POLE (7)
N.60°W 45.19' P.K. N.FACE U.POLE (8)
N.40°W 58.05' P.K. TOP OF GUARD POST (9)

DISTANCE TO L-3 2768.08' (M) RECORDED AS 2768.00' BY WAYNE COUNTY BUREAU OF TAXATION.
DISTANCE TO L-3 2768.08' (M) RECORDED AS 2768.16' AS RECORDED IN SITE SURVEY PLAN L.27004, P.392.
DISTANCE TO M-2 2672.37' (M) RECORDED AS 2672.44' AS RECORDED IN WINDRIDGE SUBDIVISION L.107, P.27.
DISTANCE TO M-2 2672.37' (M) RECORDED AS 2672.69' BY WAYNE COUNTY BUREAU OF TAXATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3
1/2" IRON ROD IN MON BOX.
SET BRASS W.C. REMON WASHER AND SURVEYOR'S CAP #41914 OVER 1/2" IRON ROD.
CORNER IS LOCATED IN PAVEMENT IN THE HAGGERTY ROAD RIGHT-OF-WAY. THIS IS NOT A COMMON CORNER.
SOUTH 127.71' MON. IN MON.BOX (1)
N.60E 55.22' P.K. N.FACE U.POLE (6)
S77°E 49.74' P.K. N.FACE U.POLE (7)
N.66°W 45.21' P.K. N.FACE U.POLE (8)
N.40°W 58.33' P.K. TOP OF GUARD POST (9)
S.65°W 66.28' SET W.C. REMON WASHER IN N.SIDE P.POLE.(10)

THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Christopher S. Lamus

Date 12/29/98

Surveyor's Michigan License No. 41914

R LCR 7 4R 1PG U J.P.L.



Vertical text on the right margin: Liber-30035, Page-255.0, 98458557LS, 12/29/1998 11:51AM