

SURVEY & REMONUMENTATION

APR 25 1995

RC 1540

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S R 8 E</u>	<u>M-5</u>
	T _____	_____
	T _____	_____
	T _____	_____
2. Property controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LI27800PA021

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-14-94 *DBJ*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, PAUL V. SCHWIMMER, in a field survey on DECEMBER 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GOVERNMENT NOTES 1815, SET BY	BOARD OF WAYNE CO. RD. COMM 1970
B. JIMMINGS - SET POST (1)	FOUND IRON IN MON. BOX (4)
ASH 14' S72°E 9 LINKS (2)	N.E. 48.39 MI. BELL POLE (9)
SUGAR 8' S 58°W 26 LINKS (3)	SLY 73.11 IRON (MEAS 73.29) (6)
	S.W. 55.79 MI. BELL POLE (10)
WAYNE CO. BUREAU OF TAXATION (1930'S)	S.W. 56.96 GAS MARKER (MEAS 60.18) (11)
IRON (4)	N.W. 69.65 GAS MARKER (MEAS 77.52) (12)
S.E. 47.40 CROSS IN CONC. SIGN POST (5)	
SLY 73.29 IRON (MEAS 73.29) (6)	ACT 74 CERTIFICATE - RC 613
S.W. 82.18 MONUMENT (7)	FD. MON BOX @ INT. 6-MILE
N.W. 51.88 24' ELM (8)	& MIDDLEBELT- CONC. MON
	(THIS CERTIFICATE IS ERRON-
	EDUS. IT SHOULD BE SOME-
	WHERE IN T1S, R9E)

\$ 13.00 MISCELLANEOUS RECORDING
 28 DEC 94 8:14 A.M. RECEIPT # 9A
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

M-5 THIS CORNER IS PERPETUATED FROM 1930 THRU PRESENT DAY BY THE EVIDENCE OF THE DESCRIBED IRON, IN ADDITION TO WITNESS (6) WHICH IS THE CLOSING CORNER FOR SECTION 7, TOWN 1 SOUTH, RANGE 9 EAST. SERIOUS PROBLEMS ARISE IN COMPARING THE 1970 WITNESSES OF (11) & (12). BASED ON THE CURRENT MEASUREMENTS, IT WOULD APPEAR THAT THE CORNER SHOULD BE MOVED WESTERLY. WE THEREFORE MEASURED THE SECTION LINES TO THE WEST (2626.94' RECORDED IN 1930'S TO 2626.64' PRESENT DAY) AND NORTH (2656.31' RECORDED IN 1930'S TO 2655.83' PRESENT DAY) TO ELIMINATE THIS DISCREPANCY. THE MEASURED ANGLE VERSUS RECORDED ANGLE WAS WITHIN 00°01'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5
 FOUND 1/2" IRON IN MONUMENT BOX
 N 45° W 77.52' GAS MARKER
 N 48° W 80.67' DISC & TAG IN N.W. SIDE OF P.P.
 N 49° E 69.17' DISC & TAG IN SE. SIDE OF P.P.
 S 67° E 136.2' FD. P.K. IN N.E. SIDE OF P.P. RESET WITH DISC
 S 48° W 76.91' FD. P.K. IN N.W. SIDE OF P.P. RESET WITH DISC
 S 48° W 60.18' GAS MARKER
 SLY 73.29' CLOSING CORNER FOR SECTION 7, T 1 S, R 9 E



THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Paul V. Schwimmer
 Surveyor's Michigan License No. 24618

Date 12-21-94

*2 E
 11 D
 MISC*