

SURVEY & RE-MONUMENTATION

RC 1216

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LI 27003 PA 594

For corners in COMMISSION

WAYNE (County) Located In: Corner Code #

1. Public Land Survey T 1 S R 8 E M 7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Register of Deeds Stamp & File Number

FOREST & WOODS REGISTERED DEEDS NEWBERRY, MI

93 DEC -3 AM 8:51 PM

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J
2	6	5	4	3	2	1			
3									
4	7	8	9	10	11	12			
5									
6	18	17	16	15	14	13			
7									
8	19	20	21	22	23	24			
9									
10	30	29	28	27	26	25			
11									
12	31	32	33	34	35	36			
13									

I, PAUL V. SCHWIMMER, in a field survey on NOVEMBER 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO G.L.O. WITNESSES REMAIN, A POST WAS SET BY JOSEPH WAMPLER IN THE ORIGINAL SURVEY OF THE TOWNSHIP WHICH WAS COMPLETED MARCH 14, 1816.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PREVIOUSLY RECORDED IN:
 1973 LIBER 18444, PG 861
 SET IRON PIPE WITH CAP (UNDER OVERPASS)
 S 70° E 91.55' *X* ON W SIDE OF 6TH PILLER, 3RD ROW (MEAS 91.95') NOTE: ONE 1930 BUREAU OF TAXATION WITNESS REMAINS
 S 45° W 52.05' *X* ON N SIDE OF 4TH PILLER, 2ND ROW (MEAS 51.99') SLY 77.33' IRON (F.D. MONUMENT AT NW CORNER SECTION 19 77.31'
 S 65° W 25.22' *X* ON N SIDE OF 6TH PILLAR, 2ND ROW (MEAS 25.22')
 1974 LIBER 18829, PG 637
 PLACED 4" CONCRETE MONUMENT WITH 5/8" ROD
 N 70° W 70.19' *X* ON STATION 79+0 (MEAS 70.19')
 S 62° W 25.22' *X* ON N COLUMN BRIDGE PIER #2 (MEAS 25.22')
 SLY 77.31' 4" CONC. MONUMENT (NW CORNER SECTION 19) (MEAS 77.31')
 1979 LIBER 20598, PG 430
 5/8" ROD IN 4" DIA CONCRETE MONUMENT
 N 70° W 70.19' *X* IN STATION STENCIL 79+00 (MEAS 70.19')
 S 62° W 25.22' CHISELED *X* N SIDE OF N COLUMN PIER No. 2 (MEAS 25.22')
 SLY 77.31' 4" DIA CONC. MON (NW CORNER SECTION 19, T1S, R9E) (MEAS 77.31')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND DAMAGED 4" CONC. MONUMENT WITH 5/8" BAR, REPLACED WITH 4" CONC. MONUMENT AND MONUMENT BOX
 S 70° E 91.95' *X* ON W SIDE 6TH PILLAR, 3RD ROW (PREVIOUS WITNESS)
 SOUTH 77.31' 4" CONC. MONUMENT AT NW CORNER SECTION 19 T1S, R9E (PREVIOUS WITNESS)
 S 45° W 51.99' *X* ON N SIDE 4TH PILLAR, 2ND ROW (PREVIOUS WITNESS)
 S 62° W 25.22' *X* ON N SIDE 6TH PILLAR, 2ND ROW (PREVIOUS WITNESS)
 N 65° W 70.19' *X* MARK AT STATION STENCIL 79+00 (PREVIOUS WITNESS)

DISTANCE TO L 7 MEASURED AS 2572.08' RECORDED IN 1930 AS 2572.38'
 DISTANCE TO B 7 MEASURED IN MASON L. BROWN SURVEY S-36595 AS 2659.32' RECORDED IN 1930 AS 2659.30'
 SET REMONUMENTATION DISC AND CAP ON MONUMENT
 THE SELECTED LOCATION IS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Paul V. Schwimmer Date NOVEMBER 11, 1993

Surveyor's Michigan License No. 24618