

**SURVEY & REMONUMENTATION**

**RC 1541**

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SEQUENCE # 1.  
L127806PA022

For corners in WAYNE (County)

Located In:	Corner Code #
1. Public Land Survey	T <u>1 S R B E</u> <u>M-9</u>
	T _____
	T _____
	T _____
2. Property controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____	
5. Private Claims _____	

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-14-94 *DBJ*  
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

I, PAUL V. SCHWIMMER, in a field survey on DECEMBER 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:  
NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- DRIG. GOVERNMENT NOTES 1815, WITNESSED BY BALESS JIMMINGS - SET POST (1)
  - B.O. S43°E 93 LINKS (2)
  - B.O. N9°W 1 CHAIN 10 LINKS (3)
  - WAYNE CO. BUREAU OF TAXATION (1930'S) MONUMENT (4)
  - E. 33.00 MONUMENT (5) S.W. 77.38 ED POLE (9)
  - S.E. 88.42 5' OAK (6) S.W. 58.53 MONUMENT (10)
  - S.E. 82.27 15' OAK (7) N.W. 45.76 40' OAK (11)
  - S. 32.02 MONUMENT (8)

BOARD OF WAYNE CO. RD. COMM  
FND MON IN BOX 1970 (4)  
S.E. 90.21 29° TWIN OAK (12)  
S.E. 46.55 DE POLE (13)  
S. 31.95 MONUMENT (8)  
S.W. 45.95 DE POLE (14)  
N.W. 74.43 DE POLE (15)

RC 1541

B. Description of corner evidence and/or method applied in restoring or reestablishing corner:

M-9 FOUND STEEL ENCASED CONCRETE MONUMENT 1.3' BELOW ROAD SURFACE. TWO WITNESSES REMAIN FROM THE 1930 RESURVEY EFFORT AND FOUR WITNESSES REMAIN FROM THE 1970 WORK. AN ADDITIONAL DIST CHECK TO M-10 STRENGTHENS THE LOCATION OF THIS MONUMENT AS BEING THAT OF M-9.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 FOUND STEEL ENCASED MONUMENT 1.3' BELOW GROUND SURFACE
- N15°E 125.32 NAIL W/ W.C.R.C. TAG IN POWER POLE
- N83°E 80.61 S.W. CORNER BUILDING
- S58°E 46.51 NAIL W/ W.C.R.C. TAG IN POWER POLE (13)
- S51°W 45.70 NAIL W/ W.C.R.C. TAG IN POWER POLE (14)
- N50°W 74.23 NAIL W/ W.C.R.C. TAG IN POLE (15)
- N50°W 209.53 N.E. CORNER OF BRICK BUILDING (DET EDISON SUBSTATION)
- S00°W 31.95 CLOSING CORNER FOR A-9 OF LIVONIA TWP
- DIST TO M-10 MEAS @ 2671.86 AND RECORDED IN THE 1930 RESURVEY EFFORT @ 2672.23

\$ 13.00 MISCELLANEOUS RECORDING  
28 DEC 94 8:14 A.M. RECEIPT # 4A  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Paul V. Schwimmer*  
Surveyor's Michigan License No. 24618

Date 12-21-94

2 R  
11 D  
MISC