

SURVEY & REMONUMENTATION

RC 1217

LI27004PA573

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in WAYNE COUNTY Located In: _____ Corner Code # _____
(County)

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/3/93 WCR
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 1 S R 9 E A-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT J. SMALLEY, in a field survey on NOVEMBER 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1815): "POST"
- WPA (1930's): "MON. SW-31"
- LCRC (1988): "FOUND MONUMENT IN HANDHOLE" (RC-905; L. 23723, P. 816)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR IN CONCRETE MONUMENT IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN LCRC AS FOLLOWS:

- NNW, 60.65'; PK NAIL, TOP OF WOOD GUARD RAIL POST (MEAS. N 4° W, 60.70')
- SE, 48.86'; PK NAIL, 16" MAPLE (PK NAIL NOT FOUND, SET NAIL AND TAG AT 48.98')
- SW, 52.17'; PK NAIL, 10" MAPLE (TREE HAS BEEN REMOVED)

2R
11D
M

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" BAR IN MONUMENT IN MONUMENT BOX IN JOY ROAD; SET "WAYNE COUNTY REMONUMENTATION" TAG AND CAP NO. 30086-26467 ON 1/2" BAR OF MONUMENT.

- N. 4° W. 60.70'; FOUND PK NAIL IN TOP OF WOOD GUARD RAIL POST.
- N. 19° E. 64.93'; SET NAIL WITH "WCR WITNESS" TAG IN TOP OF WOOD GUARD RAIL POST.
- S. 47° E. 48.98'; SET NAIL WITH "WCR WITNESS" TAG IN NE FACE OF 16" MAPLE TREE.
- S. 49° W. 61.54'; CUT CHISELED "X" IN EAST RIM OF SANITARY SEWER MANHOLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
ROBERT J. SMALLEY
Surveyor's Michigan License No. 26467