

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

WAYNE COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 S R 9 E B-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, ROBERT J. SMALLEY, in a field survey on OCTOBER 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12/3/93 TDG
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO (1815): "POST"
- WPA (1930's): "IRON N-7"
- LCRC (1988): "SET PK NAIL IN RAISED CONCRETE ISLAND USING POINTS FOUND IN RECORDED PLAT OF MELODY MANOR SUB'N (L.72, P. 43)" (RC-654; L. 20459, P. 835)

REC-3 PRG 11
1588

2R
11D
M

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND METAL DISK STAMPED "MDSH RLS 21571" SET IN RAISED CONCRETE ISLAND: CHECKED WITNESSES IN LCRC AS FOLLOWS:

- NORTH, 7.41'; NORTH EDGE OF RAISED CONCRETE ISLAND (MEAS. NORTH, 7.61')
- SOUTH, 7.63'; SOUTH EDGE OF RAISED CONCRETE ISLAND (MEAS. SOUTH, 7.43')
- EAST, 3.89'; EAST EDGE OF RAISED CONCRETE ISLAND (MEAS. EAST, 3.34')
- NE, 45.66'; SE CORNER OF UPPER PART OF CONCRETE BRIDGE RAILING (MEAS. N 25° E, 45.67')
- SE, 45.36'; NE CORNER OF UPPER PART OF CONCRETE BRIDGE RAILING (MEAS. S 25° E, 45.39')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND METAL DISK STAMPED "MDSH RLS 21571" IN RAISED CONCRETE ISLAND OF SEVEN MILE ROAD BRIDGE OVER I-275 (NOTE: IRON AND MONUMENT BOX CANNOT BE SET IN BRIDGE DECK)

- NORTH, 7.41'; NORTH EDGE OF RAISED CONCRETE ISLAND OF BRIDGE DECK.
- SOUTH, 7.43'; SOUTH EDGE OF RAISED CONCRETE ISLAND OF BRIDGE DECK.
- EAST, 48.98'; EAST EDGE OF RAISED CONCRETE ISLAND OF BRIDGE DECK.
- N. 25° E., 45.67'; SOUTHEAST CORNER OF UPPER PART OF CONCRETE BRIDGE RAILING.
- S. 25° E., 45.39'; NORTHEAST CORNER OF UPPER PART OF CONCRETE BRIDGE RAILING.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
ROBERT J. SMALLEY
Surveyor's Michigan License No. 26467

