

FEB 20 1994

RC 1219

L127004PA575

CONTRACT NO.

LAND CORNER RECORDATION CERTIFICATE
Filing requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE COUNTY (County) Located In: Corner Code #

1. Public Land Survey T 1 S R 9 E B-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/3/93 JCR
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, ROBERT J. SMALLEY, in a field survey on OCTOBER 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	•												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"
 WPA (1930's): "IRON N-19"
 LCRC (1979): "FOUND CONC. MON. (WITH 1/2" PIPE) IN MON. BOX" (RC-697; L. 20598, P. 426)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX; CHECKED WITNESSES IN LCRC AS FOLLOWS:

S 10° W, 41.96'; N.W. BOLT, BASE OF SIGNAL LITE POLE (MEAS. S 5° W, 41.96')
 N 10° E, 43.19'; S.E. BOLT, BASE OF LITE POLE (MEAS. N 3° E, 43.18')
 N 65° E, 82.14'; S.E. BOLT, BASE OF SIGNAL LITE POLE (MEAS. N 60° E, 82.14')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT (WITH 1/2" PIPE) IN MONUMENT BOX; SET 1/2" BAR WITH "WAYNE COUNTY REMONUMENTATION" TAG STAMPED "26467" INSIDE 1/2" PIPE OF MONUMENT

N. 03° E. 43.18'; CUT CHISELED "X" IN SOUTHEAST BOLT OF STREET LIGHT BASE.
 N. 60° E. 82.14'; CUT CHISELED "X" IN SOUTHEAST BOLT OF SIGNAL LIGHT BASE.
 S. 58° E. 70.83'; CUT CHISELED "X" IN NORTHEAST FLANGE BOLT ON FIRE HYDRANT.
 S. 05° W. 41.96'; CUT CHISELED "X" IN NORTHWEST BOLT OF SIGNAL LIGHT BASE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993
 ROBERT J. SMALLEY
 Surveyor's Michigan License No. 26467

RECORDED - 3 PM 12:41
 FOR THE REGISTER OF DEEDS
 WAYNE COUNTY
 JCR
 11D
 m