

FEB 20 1994

RC 1220

L127004PA576

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>1 S</u>	R	<u>9 E</u>	<u>C-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	R	_____	_____
	S	_____	R	_____	_____
3. Miscellaneous	S	_____	R	_____	_____
Property in Sec.	S	_____	R	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/3/93 JKD

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1220

I, ROBERT J. SMALLEY, in a field survey on OCTOBER 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the cornerpoints mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3		●											
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO (1816): "POST"  
WPA (1930's): "IRON NW-8"  
SURVEY (1976): "FOUND 1/2" BAR IN MONUMENT BOX" (CS-1270; L. 19593, P. 179)

SECRET - 3 PM 12:11  
FOR FILE  
MAY 1994  
210  
M

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON BAR IN MONUMENT BOX; CHECKED WITNESSES RECORDED IN CS-1270 AS FOLLOWS:

N.W., 72.90'; PK NAIL IN N.E. FACE P. POLE (FOUND PK NAIL & WCRC TAG, MEAS. S 5° W, 41.96')  
N.E., 64.55'; 10d COM. NAIL IN NW FACE P. POLE (POLE HAS BEEN REMOVED)  
S.E., 77.00'; 10d COM. NAIL IN SW FACE P. POLE (FOUND PK NAIL & WCRC TAG, MEAS. S 40° E, 79.42')

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

FOUND 1/2" IRON BAR IN MONUMENT BOX IN INTERSECTION OF SEVEN MILE ROAD AND NEWBURGH ROAD SET "WAYNE COUNTY REMONUMENTATION" TAG AND SURVEY CAP "30086-26467" ON POINT.

N. 45° W. 73.05'; FOUND PK NAIL WITH "WCRC" TAG IN NORTHEAST FACE OF UTILITY POLE.  
N. 50° E. 80.64'; SET NAIL WITH "WCR WITNESS" TAG IN NORTHWEST FACE OF UTILITY POLE.  
S. 40° E. 79.42'; FOUND PK NAIL WITH "WCRC" TAG IN SOUTHWEST FACE OF UTILITY POLE.  
S. 50° W. 81.92'; SET NAIL WITH "WCR WITNESS" TAG IN NORTHWEST FACE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Robert J. Smalley Date Nov. 30, 1993  
ROBERT J. SMALLEY  
Surveyor's Michigan License No. 26467

